

15-163-00153-00-00

Form CP-3  
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 6 1968  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Kathol Petroleum, Inc.

Complete Address: 900 Sutton Place Wichita, Kansas 67202

Lease Name Smith Well No. 1

Location SE <sup>SE SW</sup> SW Sec. 8 Twp. 9 Rge. 18 (E) XX (W) XX

County Rooks Total Depth 3500'

Abandoned Oil Well XX Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Knight Casing Pulling Company

Address: Box 405 Chase, Kansas License No. 436

Operation Completed: Hour 2-10 Day 5 Month 11 Year 1968

The Above well was plugged as follows:

Total Depth 3500' 8 5/8 csg set at 170' cwc

5 1/2 csg set at 3498' cw 100 sc cmt.

5 1/2 csg PBD 3408' with top perf. at 3225'.

Filled 5 1/2 csg with sand to 3200' ~~3200' (3200-3200)~~ dumped 5 sc cmt with dump bailer. (3150-3190).

Shutoff and recov. 430' of 5 1/2 csg.

Pumped thru 8 5/8 plug container with 20 sc gel, 5 hulls, plug and 100 sc cmt.

Max. Pres. 2000 lbs. SI pres. 2000 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo. G. Massey  
Well Plugging Supervisor

DATE 11/6/68

INV. NO. 8771-4