

15-163-02299-00-00

KANSAS

Form CP-3  
Rev. 6-4-68

P

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENCY'S REPORT

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 - -

RECEIVED  
STATE CORPORATION COMMISSION  
1/3/78  
JAN 3 1978  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Murfin Drilling Co.

Complete Address 617 Union Center Bldg., Wichita, Kansas 67202

Lease Name Werner Well No. 2

Location C SW NW NE Sec. 7 Twp. 9 Rge. (E) (W) 18

County Rooks Total Depth 3465'

Abandoned Oil Well XX Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated     

Plugging Contractor Kelso Casing Pulling

Address Box 176, Chase, Kansas 67524 License No. 683

Operation Completed: Hour 11:- A Day 30 Month 12 Year 1977

The above well was plugged as follows:

Total Depth 3465' 10 3/4 csg set 207' cwc 150 sk.

5 1/2 csg set 3456' cw 250 sk cem.

5 1/2 csg FBTD 3407' & Perf. (3202-3206)

5 1/2 csg DV tool set 1452' cwc 600 sk. No pipe recovered.

Allied Cementing Co. mixed & pumped down 5 1/2 csg with 50 sk 50-50 poz 2% -displaced

with 30 sk gel & water W/300 lbs hulls -capped with cementing plug & 100 sk

50-50 poz 2% & shutin. FPP 400 lbs.

I hereby certify that the above well was plugged as herein stated.

INDEXED  
1-4-78  
INV. NO. 6502-10

Signed: Leo Maruff  
Well Plugging Supervisor