

15-163-19280-00-00

Form CP-3  
Rev. 6-26-62

**KANSAS**  
**STATE CORPORATION COMMISSION**  
**CONSERVATION DIVISION AGENT'S REPORT**

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

*Received*  
*1/21/65*

Operator's Full Name Continental Oil Co  
Complete Address: Box 267 Great Bend, Kans  
Lease Name Thompson Well No. 7  
Location NW SE NE Sec. 6 Twp. 9 Rge. (E) (W) 18  
County Rooks Total Depth 3490  
Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A       
Other well as hereafter indicated:       
Plugging Contractor: same & Halliburton  
Address:      License No.       
Operation Completed: Hour 11:45AM Day 19 Month 1 Year 65

**The Above well was plugged as follows:**

10 3/4" 202' circulated with cement & 7" 3487' with 300 sax cement -  
& squeezed at 1080' with 300 sax & 840' with 200 sax cement & 755'  
with 225 sax cement - no pipe recovery.

2 1/2" tubing lost in hole - with string of cable tools on top - top  
of fishing tools at 6160'

Circulated hole with heavy gel mud through 2 1/2" tubing - spotted 15 sax  
cement through tubing at 540', heavy mud to 240', spotted 15 sax cement  
through tubing at 240', heavy mud to 50', cement 50' to 0'

Mudding and cementing by Halliburton Co.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**

Signed: Leson Peety  
Well Plugging Supervisor

DATE 1/21/65  
INV. NO. 541-W