

15-163-02289-00-00

Form CP-3  
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
6/19/67  
JUN 19 1967  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Operator's Full Name Union Texas Petroleum  
Complete Address: Suite B-400 1740 Broadway Denver, Colorado 80202  
Lease Name Cabbage Well No. 6  
Location NW SE SW Sec. 7 Twp. 9 Rge. 18 (E) (W) X  
County Rooks Total Depth 3504  
Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A       
Other well as hereafter indicated:       
Plugging Contractor: Santa Fe Pipe & Supply Co.  
Address: Box 562 Great Bend, Kansas License No. 574  
Operation Completed: Hour 9:45 P Day 15 Month 6 Year 1967

The Above well was plugged as follows:  
Total Depth 3504' 10 3/4 csg set at 229' cwc 125 sc.  
5 1/2 csg set at 3502' cw 150 sc. cem.  
PB 3450' and perf. 3234-38  
Filled with sand to 3200' and dumped 5 sc cement with dump bailer.  
Recov 1358' of 5 1/2 csg.  
Squeezed 10 3/4 csg with 35 sc gel and 100 sc 50-50 poz cement. Shutin pres 200 lbs.

I hereby certify that the above well was plugged as herein stated.

Signed: R. W. F. Messing  
Well Plugging Supervisor

INVOICED  
DATE 6/19/67  
INV. NO. 5419-2