

DISTRICT CONSERVATION AGENT'S REPORT

B

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION SW SE SE

SEC. 7 TWP. 9 RGE. 18 W

Dry Hole Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Cabbage 507 W. K. H. A/d/g.

Operator Grant Oil Co Address Wichita, Kans

Field _____ County Rooks

Total Depth 3721 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 240' Circulated with cement - 5 1/2" at 3521'

Cement to 3516' - Perforations at 3368' - Set plug at 3350'

with 4 sax cement - pulled 2900' 5 1/2" - filled with mud to

240', set rock and 15 sax cement - mud to 35', set rock and

10 sax cement to bottom cellar.

PLUGGING
FILE SEC 7 T 9 R 18 W
BOOK 23 LINE 22

RECEIVED
OCT 29 1952

Edson Perry
District Conservation Agent

Date 10-24-52