

KANSAS

FORM CP-3  
Rev. 1-8-82

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT REPORT

API Number 15- -

200 Colorado Derby Building  
Wichita, KS 67202

Operator's Full Name Rockett-Schusterman Oil Ace.

Complete Address 2700 1st Place - Tulsa, Okla 74103

Lease Name Cabbage Well No. 2

Location NE-SW-SW Sec. 7 Twp. 9 Rge. 18 (East) (West) (West)

County Rooks Total Depth 3501

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Allied Cementing

Address Russell, Kansas License No. \_\_\_\_\_

Operation Completed: Hour: 12:00 PM Day: 30 Month: 6 Year: 19 82

Plugging Operations attended by Agent?: All  Part  None

The above well was plugged as follows:

10 3/4" set @ 216' w/216 ex - 5 1/2" set @ 3498' w/350 ex  
Holes in casing @ 864' & 1340' - last prod in 1975 -  
hole open to 3470' -  
Ordered 450 ex 50% poz mix 60 gel 30 cc & 8 shells -  
Pumped in through 5 1/2" casing - circ out of 10 3/4" <sup>emb.</sup>  
G.P. shut in 10 3/4" - pumped in 450 ex - pressure  
to 450# PSI. Shut-in

Amount of Surface Casing: 216'

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Dennis L. Hamel  
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

Signed: \_\_\_\_\_  
Conservation Division Agent

RECEIVED  
STATE CORPORATION COMMISSION  
7/20/82  
JUL 20 1982  
CONSERVATION DIVISION  
Wichita, Kansas

7-22-82  
677-W