

15-163-03782-00-02

KANSAS

FORM CP-3
Rev. 1-8-82

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15- 48 R200 Colorado Derby Building
Wichita, KS 67202Operator's Full Name Energy Reserve Group (George Hutton)Complete Address Box 1201 - 217 N. Water St. - Wichita, KS 67201Lease Name Werner Well No. #3Location SW-NE-NW Sec. 7 Twp. 9 Rge. 18 (East) (West)County Rooks Total Depth 3802'Abandoned Oil Well ☐ Gas Well ☐ Input Well ☐ SWD Well ☒ D&A ☐Other well as hereinafter indicated ☐Plugging Contractor Allied CementingAddress Russell, Kansas License No. ☐Operation Completed: Hour: 2:00 PM Day: 17 Month: 8 Year: 19 82Plugging Operations attended by Agent?: All ☒ Part ☐ None ☐

The above well was plugged as follows:

10 3/4" (32#) @ 217' w/200 sy - 6" (18#) @ 3479 w/300 sy
4 1/2" liner @ 3484 to 3577 w/45 sy - Plug back
to 3613' - 4 1/2" @ 3208' to surface w/200 sy
2 3/8" fiberglass to 3613' w/200 sy cement - top
of cement @ 1843' - Perf. fiberglass tubing 3475-76;
3493-99; 3520-21; 3543-46; 3581-84;

Tubing parted @ 454' - has 2" to 2 1/2" stringer w/
inside diameter of 1" - Pumped 50 sy cement through tubing
pulled tubing & pumped additional 110 sy cement & 4 hulls in
Amount of Surface Casing:
4 1/2" csq - Max P.S.T. 600' - Shut-in P.S.T. 200' -

I hereby certify that the above plugging instructions were given as herein stated.

Checked annulus & found cement to top of Pipe.
 Signed: Dennis L. Hamel
 Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

INVOICED

DATE 11-15-82INV. NO. 1563-W

Signed: _____

Conservation Division Agent

RECEIVED
10/15/82
OCT 15 1982STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas