

15-163-03455-00-00

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 66-29

LOCATION NW NW SW

SEC. 5 TWP. 9 RGE. 18

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease H Hilgers

Operator Heathman-Honaker Address Wichita, Kans

Field _____ County Rooks

Total Depth 3510' Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 151' Circulated with cement. 4 1/2" at 3500'
Cement to 3475' - Heavy mud to 3225' - Wood plug and 25 sax
Cement at 3225' - Heavy mud to 151', wood plug, rock and
15 sax cement - Heavy mud to 25', wood plug and 10 sax cement

3/12/49

[Signature]
District Conservation Agent

Date 3 - 9 - 49

PLUGGING
FILE SEC 5 T 9 R 18
BOOK PAGE 66 LINE 29