

15-163-03352-00-00

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

10/18/62

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Okmar Oil Co

Complete Address: 820 Union Natl Bk Bldg Wichita, Kansas

Lease Name x~~Hanna~~ Holmes Well No. 1

Location NE SW NW Sec. 5 Twp. 9 Rge. (E) (W) 18

County Rooks Total Depth 3494 ~~3524~~

Abandoned Oil Well x Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Southwest Casing Pulling

Address: Great Bend, Kansas License No. 399

Operation Completed: Hour 9AM Day 4 Month 10 Year 62

The Above well was plugged as follows:

8 5/8" 200' circulated with cement - 5 1/2" 3491' with 100 sax cement.
Filled with sand to 3480', set 4 sax cement with dump bailer - pulled
1193' 5 1/2" to 550', tried to circulate hole with mud - hole pressured up
to 1250# - pulled 5 1/2" to 360', circulated hole with mud (25 sax Gel),
displaced 20 sax cement through 5 1/2" at 360', heavy mud to 160', displaced
20 sax cement through 5 1/2" at 160', heavy mud to 35', cement 35' to 0'
Mudding and cementing by Southwest Casing Pulling pump truck.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 10/10/62
INV. NO. 5816-11