

*R*

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
211 North Broadway  
Wichita, Kansas

FILE NO. 150-21

LOCATION NE NW NW

SEC. 17 TWP. 9 RGE. 18

Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. 2 Lease Stahl

Operator Sinclair Oil & Gas Co Address Box 551 Chase, Kans

Field \_\_\_\_\_ County Rooks

Total Depth 3647 Feet.

Plugging Contractor West Supply Co

Plugging Contractor's License No. 14

Address \_\_\_\_\_

(Describe briefly the manner in which the well was plugged)

10 3/4" at 307' circulated with cement - 7" at 3640' with 150

sax cement behind. Perforated at 3545'

sand to 3540', set plug and 4 sax cement at 3540', pulled approx

1100' 7" - mud to 305', set rock and 20 sax cement, mud to 30',

set rock and 10 sax cement to bottom cellar.

**PLUGGING**  
FILE SEC 17 T 9 R 18 W  
BOOK PAGE 15 LINE 21

RECEIVED  
CORPORATION COMMISSION  
OCT 20 1955  
10-20-55  
CONSERVATION DIVISION  
Wichita, Kansas

*Leon Lee*  
District Conservation Agent  
Date 10-17-55