

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 62-10
LOCATION SW NW NE
SEC. 17 TWP. 9 RGE. 18

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 2 Lease Elizabeth

Operator Frank J. Black Address Box 150 Mc Pherson, Kans

Field _____ County Rooks

Total Depth 3528 Feet.

Plugging Contractor Forbes Casing Pulling

Plugging Contractor's License No. 49

Address _____

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 1459' circulated with cement - 5 1/2" 3527' with 100 sax
cement behind.

Filled with sand to 3520', set 4 sax cement with dump bailer, pulled
2935' 5 1/2" to 1000', circulated hole with Gel (20 Sax) at 1000',
displaced 20 sax cement through 5 1/2" at 650', heavy mud to 200',
displaced 20 sax cement through 5 1/2", heavy mud to 35', set rock
and 10 sax cement to bottom cellar.

Mudding and cementing by Forbes pump truck.

John Hanna

By *E.P. Lester*
District Conservation Agent

Date 12-13-57

PLUGGING
FILE REC 17 T 9 R 18W
BOOK PAGE 62 LINE 10

RECEIVED
STATE CORPORATION COMMISSION
DEC 17 1957
12-17-57
CONSERVATION DIVISION
Wichita, Kansas