

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 62-9

LOCATION NW NW NE

SEC. 17 TWP. 9 RGE. 18

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Elizabeth

Operator Fronk J. Black Address Box 150 Mc Pherson, Kans

Field _____ County Rooks

Total Depth 3524 Feet.

Plugging Contractor Forbes Casing Pulling

Plugging Contractor's License No. 49

Address _____
(Describe Briefly the manner in which the well was plugged)

8 5/8" at 1450' circulated with cement - 5 1/2" 3520' with 100 sax
cement behind.

Filled with sand to 3510', set 4 sax cement with dump bailer, pulled
2990' 5 1/2" to 1000', circulated hole with heavy mud (Gel), displaced
20 sax cement through 5 1/2" at 650', heavy mud to 200', displaced 20
sax cement through 5 1/2" - heavy mud to 35', set rock and 10 sax
cement to bottom cellar.

Used Forbes Co pump truck for mudding and cementing.

Edson Lee
District Conservation Agent

RECEIVED
STATE CORPORATION COMMISSION
12-14-57
DEC 14 1957

Date ~~12-9-57~~ 12-9-57

CC. CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC. 17 T. 9 R. 18
BOOK PAGE 62 LINE 9