

*70*  
KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

STATE CORPORATION COMMISSION  
MAY 10 1965  
5-10-65  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Fender Pipe & Supply  
Complete Address: Box 302 Russell, Kans  
Lease Name Baumgartner Well No. 1  
Location SW SE SE Sec. 17 Twp. 9 Rge. (E) (W) 18  
County Rooks Total Depth 3570  
Abandoned Oil Well x Gas Well      Input Well      SWD Well      D & A       
Other well as hereafter indicated:       
Plugging Contractor: Knight Casing Pulling Co  
Address: Chase, Kans License No. 436  
Operation Completed: Hour 7PM Day 6 Month 5 Year 65

The Above well was plugged as follows:

8 5/8" 236' circulated with cement - 5 1/2" 3562' with 175 sax cement & squeezed at 1492' with 300 sax cement.  
Sand back to 3330', set 4 sax cement with dump bailer - shot 5 1/2" at 401' - circulated hole with heavy gel mud through 5 1/2" at 401' ( 21 sax Gel) displaced 20 sax cement through 5 1/2" at 401', heavy mud to 190', displaced 20 sax cement through 5 1/2" at 190', heavy mud to 35', cement 35' to 0'

Mudding and cementing by Knight Company pump truck.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *Edon Petty*  
Well Plugging Supervisor

DATE 5/10/65  
INV. NO. 1135-W