



DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 123-24

LOCATION NE-NE-SW

SEC. 17 TWP. 9 RGE. 18-W

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Mary Rusicka

Operator L.B. Lawrence Address P.O. Box #17 - Great Bend - Kans

Field Atlantic Refining Co. County Roos As - Atlantic Refining Co - Plugging

Total Depth 3580 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 1/2 - 1509 ft - Cemented all around.
5/8" casing set at 3559 ft - cemented with 100 sacks of
cement & tested - No Oil - Filled hole back from
bottom to 3558 ft & put in 6 sacks of cement on bottom
with Mump Bailey - Shut off & recorded 2150 ft of 3/4" casing
filled hole with mud to 1795 ft set Plug & 15 sacks cement
on top - Surface Plug 20 ft below the surface & 5 sacks
of cement - Mud between Plugs

Bill Morgan
Pipe Puller's Pluggin

C. D. Stough
District Conservation Agent

Date 9-2-3-1917

PLUGGING
FILE SEC-17 T-9 R-18W
BOOK PAGE 123 LINE 24