

15-163-03463-00-02


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
300 Bitting Building
Wichita, Kansas

OR
FORMATION PLUGGING RECORD Strike out upper line when reporting plugging of formations.

Rooks County. Sec. 7 Twp. 9 Rge. 18 (E) (W)
Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines. SW $\frac{1}{4}$ NW $\frac{1}{4}$ SE $\frac{1}{4}$
Lease Owner Lee Phillips, Jr., Perry Hanson, and Prime Drilling
Lease Name Cabbage Well No. 1 Co. Co.
Office Address 3111 Apco Tower, Oklahoma City, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed December 8, 19 49
Application for plugging filed December 8, 19 49
Application for plugging approved December 8, 19 49
Plugging commenced December 8, 19 49
Plugging completed December 8, 19 49
Reason for abandonment of well or producing formation.....



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production..... 19.....
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas
Producing formation..... Depth to top..... Bottom..... Total Depth of Well 3610 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	224	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from.....feet to.....feet for each plug set.

Filled hole with heavy drilling mud to 225', set bottom plug at 224', cemented with 15 sacks cement, filled hole with heavy drilling mud to 30' set top plug at 30', cemented with 10 sacks cement.

RECEIVED

12/16/49
DEC 16 1949

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Prime Drilling Company
Address 3111 Apco Tower, Oklahoma City, Oklahoma

STATE OF OKLAHOMA, COUNTY OF OKLAHOMA, ss.

L. J. Kruse (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L. J. Kruse
Oklahoma City, Oklahoma
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of December 19 49
Hazel Purley
Notary Public.

My commission expires March 13, 1953

22-2625 2-48-15M

FILE SEC 7 T 9 R 180
BOOK PAGE 189 LINE 19

15-163-03463-00-00

Lee Phillips, Jr., Perry Hanson & Prime Drilling Co.

CABBAGE NO. 1

SW/4 NW/4 SE/4, Section 7-9S-18W,
Rooks County, Kansas

<u>Formation</u>	<u>From</u>	<u>To</u>	<u>Remarks</u>
Surface clay	0	30	
Sand	30	50	
Shale	50	224	8 5/8" C.S.A. 224', W/125 Sacks
Shale	224	375	Cement
Shale & shells	375	565	
Sand	565	610	
Sand & shale	610	630	
Shale & shells	630	790	
Sand & shale	790	840	
Shale & shells	840	930	
Sand	930	1090	
Red bed, shale & shells	1090	1437	
Anhydrite	1437	1477	
Red bed	1477	1550	
Shale & shells	1550	1780	
Salt & shells	1780	1900	
Shale & shells	1900	1935	
Shale & lime	1935	2000	
Lime & shale	2000	2085	
Lime	2085	2245	
Lime & shale	2245	2580	
Shale & Lime	2580	2750	
Lime & shale	2750	2765	
Shale & shells	2765	2825	
Shale & lime	2825	2955	
Lime & shale	2955	3010	
Shale & lime	3010	3030	
Lime	3030	3445	
Lime & shale	3445	3502	
Lime, Shale & chert	3502	3570	
Conglomerate	3570	3610	No casing set.
Total Depth		3610	

I hereby certify the foregoing to be a true and accurate Driller's log of the formations encountered in the above well.

PLUGGING
 FILE SEC 7-T-9-R18W
 BOOK PAGE 129-19

PRIME DRILLING COMPANY

By L. J. Kruse
 L. J. Kruse, Asst. Secy.

Subscribed and sworn to before me this 15th day of December, 1949

Wesley Turley
 Notary Public

DEC 16 1949
 STATE COMMISSION
 KANSAS

My commission expires: March 13, 1953