

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Rooks County. Sec. 7 Twp. 9 Rge. 18W (~~25W~~) (W)
Location as "NE/CNW/SW" or footage from lines C S/2 SW NW

Lease Owner F. P. Hambright

Lease Name Werner Well No. 1

Office Address Plainville, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed February 2, 19 50

Application for plugging filed September 28, 19 59

Application for plugging approved September 28, 19 59

Plugging commenced November 21, 19 59

Plugging completed November 21, 19 59

Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3482 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8 5/8" | 162' | |
| | | | | 5 1/2" | 3480' | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

8 5/8" at 250' circulated with cement - 5 1/2" 3470' with 100 sacks cement - 5 1/2" squeezed and circulated from 1000' to 0' with cement squeeze job - no pipe recovery - tools lost in hole at 2000' on clean out job.
Pumped 75 sacks cement in hole on 10-21-59 pump pressure 1000# - pressure broke down at 70 sacks - top of cement at 440' - pumped hole full cement from 440' to 0' 46 sacks cement - open end connection - 11-21-59
Cementing by Sun Cementing Company

RECEIVED
STATE CORPORATION COMMISSION
AUG 5 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sun Cementing Company
Address Hays, Kansas

STATE OF Kansas, COUNTY OF Barston, ss.
James W. Muffat (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James W. Muffat
(Address) _____

SUBSCRIBED AND SWORN TO before me this 2nd day of August, 19 68

My commission expires May 23, 1970
Gene Livingston Notary Public.

MUEGROVE PETROLEUM CORPORATION

WELL LOG

Wormer #1, C 3/2 SW NW 7-9-18
Rooks County, Kansas

COMMENCED: 1-21-50
COMPLETED: 2-3-50

| | | |
|------|------|-----------------------|
| 0 | 95 | Soil, Sand, shells |
| 95 | 170 | Shale and shells |
| 170 | 625 | Shale and shells |
| 625 | 865 | Sand and shale |
| 865 | 1365 | Shale |
| 1365 | 1490 | Shale and shells |
| 1490 | 1490 | Anhydrite |
| 1490 | 1545 | Shale and lime shells |
| 1545 | 1675 | Shale and shells |
| 1675 | 1775 | Lime |
| 1775 | 1775 | Lime and shale |
| 1775 | 2075 | Lime and shale |
| 2075 | 2180 | Lime and shale |
| 2180 | 2300 | Lime and shale |
| 2300 | 2325 | Lime |
| 2325 | 2365 | Lime |
| 2365 | 2412 | Shale and lime |
| 2412 | 2525 | Lime and shale |
| 2525 | 2610 | Lime broken |
| 2610 | 2630 | Lime broken |
| 2630 | 2672 | Shale and lime shells |
| 2672 | 2760 | Shale and lime shells |
| 2760 | 2790 | Shale |
| 2790 | 2825 | Lime |
| 2825 | 2890 | Shale and lime |
| 2890 | 2980 | Shale and lime |
| 2980 | 2965 | Lime and shale |
| 2965 | 3113 | Lime and shale |
| 3113 | 3156 | Lime |
| 3156 | 3225 | Lime |
| 3225 | 3255 | Lime |
| 3255 | 3308 | Lime |
| 3308 | 3345 | Lime |
| 3345 | 3375 | Lime |
| 3375 | 3411 | Lime |
| 3411 | 3452 | Lime |
| 3452 | 3483 | Lime |
| 3483 | | Rotary Total Depth |

RECEIVED
STATE CORPORATION COMMISSION
9/28/54
SEP 28 1954
CONSERVATION DIVISION
Wichita, Kansas

CASING RECORD

Set 3-3/8" surface casing at 162', cemented with 90 sacks cement.

Set 5-1/2" casing at 3430', cemented with 75 sacks cement.

STATE OF KANSAS }
COUNTY OF SEDGWICK } SS

I hereby affirm that the above and foregoing is a true and correct copy of the log of the #1 Wormer located C 3/2 SW NW 7-9-18, Rooks County, Kansas.

AMSCHE - MUEGROVE DRILLING COMPANY

By: *H. R. Jensen*

Subscribed and sworn to before me this 7th day of February, 1950.

Martha Goy
Notary Public

My commission expires September 12, 1953

PLUGGING

File Sec. 7 T 9 R-18a

Book Page 4 Line 35