

15-163-02289-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Rooks County. Sec. 7 Twp 9 Rge. (E) 18 (W)
Location as "NE/CNW%SW%" or footage from lines NW SE SW
Lease Owner Union Texas Petroleum
Lease Name Gabbage Well No. 6
Office Address 1740 Broadway, Denver, Colorado
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved May 19 19 67
Plugging commenced June 12 19 67
Plugging completed June 15 19 67
Reason for abandonment of well or producing formation depleted

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3504' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10-3/4"	229'	none
				5-1/2"	3502'	1369.55'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

3504' - 3450' - plug
3450' - 3200' - sand
3200' - 3160' - 5 sacks cement
3160' - 225' - pumped 25 sacks gel mud
225' - base - pumped 100 sacks cement

RECEIVED
STATE CORPORATION COMMISSION
715 167
JUL 5 1967

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Santa-Fe Pipe & Supply Co., Inc.
Address P. O. Box 562, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

T. L. Nutt (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) T. L. Nutt

P. O. Box 562, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 30 day of June, 19 67

My commission expires July 31, 1970

Mary M. Guesnier
Notary Public.

15-163-02284-00-00
COPY


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
 412 Union National Bk. Bldg., Wichita, Kansas

Company - H H & B DRILLING CO., INC.
 Farm - Cabbage No. 6

SEC. 7 T. 9 R. 18E
 NE/4 SE/4 SW/4

Total Depth. 3504'
 Comm. 7-25-47 Comp. 8-20-47
 Shot or Treated.
 Contractor. H H & B Drilling Co., Inc.
 Issued. 11-29-47

County. Rooks
 KANSAS



Elevation. _____

Production. Pot. • 50 BO

CASING:

10 3/4" 222' Cem 125 sx.
 5 1/2" 3502' Cem 150 sx.

Figures indicate Bottom of Formations.

clay & shale	235
shale	255
shale	750
shale & sand	1434
anhydrite	1467
shale	1910
shale & lime	2040
lime & shale	2835
shale & lime	2930
shale	3010
shale & lime	3100
lime & shale	3260
lime	3460
shale & lime	3490
red bed & shale	3504
Total Depth	

TOPS: (KB)

Anhydrite	1434
Lansing	3254
Arbuckle	3500

RECEIVED
 STATE CORPORATION COMMISSION
 5/22/67
 MAY 22 1967
 CONSERVATION DIVISION
 Wichita, Kansas