

15-163-00427-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD

Books _____ County, Sec. 7 Twp. 9 Rge. 18 (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW-SE-SE _____

Lease Owner Grant Oil Co.

Lease Name Cabbage Well No. 1

Office Address 507 WKH Bldg. Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) oil

Date well completed 19 _____

Application for plugging filed Oct. 17 19 52

Application for plugging approved Oct. 17 19 52

Plugging commenced Oct. 20 19 52

Plugging completed Oct. 24 19 52

Reason for abandonment of well or producing formation went dry

If a producing well is abandoned, date of last production Oct. 9 19 52

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Petty

Producing formation Arbuckle Depth to top 3350 Bottom 3495 Total Depth of Well 3495 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
surface	water	0	240'	3 5/8	240'	none
arbuckle	oil	3709	3721	5 1/2	3521	2920

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with sand from 3495' to 3350'. Dumped 4 sacks of cement. Pipe was shot of at 2020' and pulled. Filled with heavy mud to 240' of surface. Put in 10 ft. of rock. Mixed and ran 15 sacks of cement. Filled hole with mud to 35' of top. Put in 5' of rock bridge. Ran 10 sacks of cement. This filled to bottom of cellar.

Received
11/6/52

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Grant Oil Co.
Address 507 W-K-H Bldg. Wichita, Kansas.

STATE OF Kansas, COUNTY OF Barton, ss.

I, Paul Pfeifer (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Paul Pfeifer
2536 W. E. Apple Street Barton
(Address)

SUBSCRIBED AND SWORN to before me this 4th day of November, 1952

Ray Gillig
Notary Public.

My commission expires 9-4-54

PLUGGING
FILE SEC 2 T 2 R 18
BOOK PAGE 56 LINE 27

15-163-00427-02-06

CABBAGE NO. 1

SW/4 SE/4 SE/4 Sec. 7-9S-18W, Rooks County, Kansas

Rigging up Rotary Tools 4/15/52
Tearing down Rotary Tools 4/28/52

Run 6 Jts. 8 5/8" surface pipe. Set at 240' and cemented with 150 sx cement

Run 108 Jts. 5 1/2" casing. Set at 3521' and cemented with 75 sx cement

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>
Sand, shale and shells	0	240
Shale and sand	240	957
Anhydrite	957	995
Shale	995	1324
Sand, Shale, shells and redbed	1324	1435
Shale and redbed	1435	1520
Anhydrite	1520	1525
Shale and shells	1525	2160
Shale and lime	2160	2285
Shale and lime streaks	2285	2723
Shale and shell lime streaks	2723	2986
Shale and lime streaks	2986	3085
Shale and shell lime streaks	3085	3145
Shale and lime	3145	3262
Broken lime	3262	3305
Shale and lime	3305	3377
Lime shale streaks	3377	3398
Lime	3398	3465
Lime and shale	3465	3573
Conglomerate	3573	3722 Total Depth

I, W. A. Grant, hereby certify that the above log is true and correct, to the best of my knowledge and belief.

Subscribed and sworn to before me this 5th day of November, 1952.

Notary Public

My commission expires: Feb. 29, 1956

PLUGGING
FILE SEC 7 T 9 R 182
BOOK PAGE 55 LINE 27

FILED
NOV 16 1952
CONSERVATION
Wichita, Kansas