

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Rooks County, Sec. 6 Twp. 9S Rge. (E) 18(W)

Location as "NE/CNW/SW" or footage from lines NW SE NE

Lease Owner Continental Oil Company

Lease Name E. A. Thompson Well No. 7

Office Address Box 267, Great Bend, Kansas 67530

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed 10-10-19 51

Application for plugging filed 01-07-19 65

Application for plugging approved 01-12-19 65


Plugging commenced 01-19-19 65

Plugging completed 01-19-19 65

Reason for abandonment of well or producing formation The loss of drilling and fishing equipment in the hole and it could not be

If a producing well is abandoned, date of last production 9-27-64 19 recovered

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Arbuckle Depth to top 3486 Bottom 3490 Total Depth of Well 3490 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Arbuckle	Oil & Water	3487	3490	10 3/4"	199'	None
				7"	3515'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Circulated hole with seven sacks of mud, spotted 15 sacks of cement at 540', 15 sacks at 240', and 15 sacks at 60' filling hole to surface.

RECEIVED  
STATE CORPORATION COMMISSION  
1/26/65  
JAN 26 1965  
CONSERVATION DIVISION  
Wichita, Kansas

Name of Plugging Contractor The Halliburton Company  
Address Hays, Kansas

STATE OF Kansas, COUNTY OF Barton, ss. L. E. Powell (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
Box 267, Great Bend, Kansas 67530 (Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of January, 19 65

My commission expires August 16, 1967

[Signature]  
Kenneth J. Querry Notary Public.

Kansas State Corp. Comm. File

CONTINENTAL OIL COMPANY

-E. A. THOMPSON NO. 7-  
NW SE NE, Sec. 6, T9S, R18W  
Rooks County, Kansas

DRILLER'S LOG

Contractor:  
Lohmann-Johnson Drilling Company  
Evansville, Indiana

Total Depth: 3490'

	0 - 60 - Clay & Sand
	60 - 90 - Shale
	90 - 730 - Shale & Shells
	730 - 1310 - Shale & Shells
	1310 - 1463 - Shale & Red Bed
	1463 - 1492 - Anhydrite
	1492 - 1740 - Shale & Shells
	1740 - 1990 - Shale & Lime
	1990 - 2293 - Shale & Lime
	2293 - 2460 - Lime
	2460 - 2580 - Shale & Lime
	2580 - 2864 - Shale & Shells
	2864 - 3237 - Lime & Shale
<u>Cored Footage:</u>	3237 - 3238 - Green Shale
	3238 - 3266 - Gray Lime w/Shale Streaks
	3266 - 3269 - Black to Gray Shale
	3269 - 3272 - Green Shale w/Lime Streaks
	3272 - 3273 - Red Shale
	3273 - 3277 - Green Shale
	3277 - 3288 - Gray Lime
	3288 - 3296 - Red & Green Shale
	3296 - 3303 - Lime w/Green Shale Streaks
	3303 - 3306 - Green Shale
	3306 - 3309 - Gray Lime
	3309 - 3314 - Green to Red Shale
	3314 - 3318 - Lime
	3318 - 3323 - Lime w/Shale Streaks
	3323 - 3328 - Lime
	3328 - 3331 - Lime w/Green & Black Shale Streaks
	3331 - 3338 - Lime
	3338 - 3348 - Lime Streaked w/Gray Shale & Chert
	3348 - 3351 - Lime
	3351 - 3357 - Gray Shale
	3357 - 3369 - Black Shale
	3369 - 3387 - Gray, White & Brown Lime
	3387 - 3392 - Gray to Black Shale
	3392 - 3405 - Lime
	3405 - 3408 - Limey Shale
	3408 - 3418 - Lime
	3418 - 3430 - Black, Gray & Green Shale
	3430 - 3440 - Lime
	3440 - 3448 - Gray to Tan Lime w/Shale Streaks
	3448 - 3449 - Green Shale
	3449 - 3472 - Lime w/Shale Streaks
	3472 - 3484 - Green Shale
	3484 - 3488 - Green Shale & Gray Lime
	3488 - 3490 - Brown Dolomite

**RECEIVED**  
STATE CORPORATION COMMISSION  
2/19/65  
FEB 19 1965

CONSERVATION DIVISION  
Wichita, Kansas

ARC-MED  
2-18-65