

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-163-01574-00-00
API NUMBER N/A ZAP KCC

LEASE NAME REMPE, Ernest J.

WELL NUMBER 1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

4950 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 28 TWP. 9S RGE. 18 (E) or (W)

COUNTY ROCKS

Date Well Completed 8-1-47

Plugging Commenced 5-20-98

Plugging Completed 5-20-98

LEASE OPERATOR PROSPECT OIL & GAS INC

ADDRESS Box 837 Russell, Kansas

PHONE# (785) 483-6266 OPERATORS LICENSE NO. 6627

Character of Well OIL

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 5-20-98 (date)

by NA (KCC District Agent's Name).

Is ACO-1 filed? NA if not, is well log attached? _____

Producing Formation ARBUCKLE Depth to Top 3594 Bottom 3597 T.D. 3597

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
ARBUCKLE	WATER	3594	3597	8 3/8	1496'	NONE
LANSING	NA	3341	NA	5 1/2	3595'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each set:
2" TUBING @ 300' SPOT 50 SY W 100# HULLS DISPLACE TO 1150' SHOT TUBING OFF @ 1100'. MIXED 120 SY CEMENT W/ 300# HULLS - CEMENT CIRC TO SURFACE, PULLED TUBING 5 1/2 SWAGE, MIXED 180 SY CEMENT W/ 200# HULLS

Name of Plugging Contractor ALLIED CEMENTING CO., INC License No. N/A

Address Box 31 Russell Kansas 67605

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: PROSPECT OIL & GAS INC

STATE OF KANSAS COUNTY OF Russell, ss.

BRAD HUTCHISON

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) [Signature]

(Address) Box 837 Russell KS 67605

SUBSCRIBED AND SWORN TO before me this 28 day of September, 19 98

Ruby M Nowak
Notary Public

My Commission Expires: 6-15-99

NOTARY PUBLIC - State of Kansas
RUBY M. NOWAK
My Appt. Exp. 6-15-99
Form CP-4 Revised 05-88