

LEASE NAME Paradise Creek (Hayes #2)

WELL NUMBER 2

1650 Ft. from S Section Line

990 Ft. from E Section Line

SEC. 28 TWP. 9S RGE. 18W (E) or (W)

COUNTY Rooks

Date Well Completed 10-24-47

Plugging Commenced 06/25/03

Plugging Completed 06/25/03

RECEIVED
6/27/03
JUN 27 2003

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

KCC WICHITA

LEASE OPERATOR American Energies Corporation

ADDRESS 155 N. Market, Suite 710, Wichita, KS 67202

PHONE# (316) 263-5785 OPERATORS LICENSE NO. 5399

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 6/25/03

by Herb Deines (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? No - Sent previously

Producing Formation Lansing Depth to Top 3320 Bottom 3579 T.O. 3582

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Surface		0	185'	8"	185'	None
Production		0	3579'	5"	2579'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, - from feet to feet each set

Ran tubing to 2000', spot 80 sx cement 60/40 poz with 10% gel with 300# hulls. Pulled to 1000', circulated cement with 75 sx. TOH with tubing. Pumped 90 sx down casing. SQ @ 400#, 200# SI. Pumped 50 sx down backside. 200# SIP. 100# Job complete

Name of Plugging Contractor Allied Cementing License No. N/A
Address P.O. Box 31, Russell, Kansas 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: American Energies Corporation

STATE OF Kansas COUNTY OF Sedgwick, ss.

Alan L. DeGood, President

I, Alan L. DeGood, (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Alan L. DeGood

(Address) 155 N. Market, Suite 710,

Alan L. DeGood, President
155 N. Market, Suite 710,

SUBSCRIBED AND SWORN TO before me this 26th day of June, 19 2003

Melinda S. Wooten

Notary Public
Melinda S. Wooten

My Commission Expires: 3-12-04
USE ONLY ONE SIDE OF EACH FORM



ALLIED CEMENTING CO., INC. 13387

Federal Tax I.D.#

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:

R

RECEIVED
6/27/03
JUN 27 2003
KCC WICHITA

DATE <u>6/25/03</u>	SEC.	TWP.	RANGE	CALLED OUT	ON LOCATION <u>9:00 A.M.</u>	JOB START	JOB FINISH <u>4:30 P.M.</u>
LEASE <u>Paradise Creek</u>	WELL # <u>2</u>	LOCATION <u>Prille 1w 2nd N 14</u>		COUNTY <u>Rock</u>	STATE <u>Ks</u>		
OLD OR NEW (Circle one)							

CONTRACTOR LEON'S

OWNER

TYPE OF JOB OH

HOLE SIZE

T.D.

CASING SIZE 5 1/2

DEPTH

TUBING SIZE 2 3/4

DEPTH

DRILL PIPE

DEPTH

TOOL

DEPTH

PRES. MAX

MINIMUM

MEAS. LINE

SHOE JOINT

CEMENT LEFT IN CSG.

PERFS.

DISPLACEMENT

EQUIPMENT

PUMP TRUCK CEMENTER Dan# 3166 HELPER Shane

BULK TRUCK

254 DRIVER Scott

BULK TRUCK

DRIVER

CEMENT

AMOUNT ORDERED 300 4040 1000 Gel3 HallsUSED 295 SR 3 Halls

COMMON

177

@ 75

1265⁵⁰

POZMIX

118

@ 30

448⁵⁰

GEL

21

@ 10

210⁵⁰

CHLORIDE

@

HALLS

3

@ 18

54⁵⁰

HANDLING

300

@ 15

345⁵⁰

MILEAGE

50/SR/MILE

645⁵⁰TOTAL 2967⁵⁰

REMARKS:

SERVICE

Tbg @ 2000 Spot 8000 w/ 3 Halls
Parted to have CIP cement w/
2500 Cement out w/ tbg.
5000 - 9000 4000 200 Spotting
Amounts: 5000 2000 1000 3000

DEPTH OF JOB

PUMP TRUCK CHARGE

475⁵⁰

EXTRA FOOTAGE

@

MILEAGE

43

@ 30

150⁵⁰

PLUG

@

TOTAL 625⁵⁰CHARGE TO: American Energy

STREET

CITY STATE ZIP

FLOAT EQUIPMENT

TOTAL

To Allied Cementing Co., Inc.

You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX

TOTAL CHARGE

DISCOUNT IF PAID IN 30 DAYS

SIGNATURE

PRINTED NAME