

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Rooks County. Sec. 28 Twp. 9S Rge. (E) 18 (W) 330' FNL & 990' FWL

Location as "NE/CNW/SW" or footage from lines
Lease Owner Cities Service Oil Company
Lease Name Baldwin Well No. 2
Office Address Box 553 Russell, Kansas 67665
Character of Well (completed as Oil, Gas or Dry Hole) Oil then deepened for SWD
Date well completed Oil 8-9-47 SWD 1-12 19 52
Application for plugging filed 5-10- 19 66
Application for plugging approved 5-11- 19 66
Plugging commenced 5-11-m 19 66
Plugging completed 5-13- 19 66
Reason for abandonment of well or producing formation Became non-commercial -
was deepened for SWD - now no longer needed

If a producing well is abandoned, date of last production - 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Leo Massey
Producing formation SWD Arbuckle Depth to top 2582' Bottom 3957' Total Depth of Well 3957 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	1520'	None
				5 1/2"	3583'	2294'
				4 1/2"	125'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with sand 2370' to 2340'
Dumped 5 sacks cement 2340' to 2315'
Shot off 5 1/2" casing at 2296' and pulled 74 Joints (2294')
Filled with mud to 450'
Placed 10' of rock bridge to 440'
Dumped 25 sacks cement and then filled with 10 sacks mud to 40'
Placed 10' rock bridge plug and filled to base of cellar with 10 sacks cement

RECEIVED
STATE CORPORATION COMMISSION

5/20/66
MAY 20 1966

CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton Company
Address Hays, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.
M. M. Hardin (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) M. M. Hardin

Box 553 Russell, Kansas 67665
(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of May, 19 66

My commission expires 10-5-68

James F. Kyger

Notary Public.

15-163-03826-00-01

WELL RECORD

Company Cities Service Oil Co. Well No. 2 Farm Baldwin
 Location 330' South and 990' East of NW Cor. Sec. 28 T. 9 R. 16W
 Elevation 2162 County _____ Rocks _____ State Kansas
 Deepening Dec. Comm. December 24, 1951 Contractor Felger Drilling Company
 Deepening Jan. Comp. January 12, 1952 Acid 2000 gals. 1-22-52
 T. D. 3957' Initial Prod. Input Test: 150 bbls. water per hour.

DEEPENING FOR S. W. D. WELLCASING RECORD:

8-5/8" @ 1520' cem. 750 sk cement
 5-1/2" @ 3583' cem. 150 sk cement

125' of 4-1/2" liner at 3648' with
 50 sacks cement.

FORMATION RECORD:

Old T. D. 3595
 line 3595-3679
 line, hard 3705
 line 3957 T. D.

Top Arbuckle 3582'
 Penetration 375'
 Total Depth 3957'

Input 15 bbls. per hour.

1-22-52 Acidized 2000 gals.

Input 150 bbls. water per hr.
 after acid.

5-7-54 Acidize 3930-3660
 w/ 5000 gal 15% acid

5-31-55 C.O. acidized 3630-3930
 w/ 5000 gal 15% acid

RECEIVED
 STATE CORPORATION COMMISSION
 5/20/66
 MAY 20 1966
 CONSERVATION DIVISION
 Wichita, Kansas