

15-163-22438-00-00

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Rooks SEC. 28 TWP. 9S RGE. 18 ~~W~~
 Location as in quarters or footage from lines:
4950' from South Section line and 3360' from East Section line

Lease Owner The Gene Brown Company
 Lease Name Carman Well No. 1
 Office Address 407 South Main
 Character of Well (Completed as ~~Oil or Gas~~ Dry Hole): Dry hole
 Date Well Completed 9-11-84
 Application for plugging filed Verbal
 Plugging commenced 8-31-84
 Plugging completed 9-11-84
 Reason for abandonment of well or producing formation
non-productive

Locate Well
 correctly on above
 Section Platt.

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Dennis Hamel
 Producing formation Arbuckle Depth to top 3599 bottom 3651 T.D. 3651
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
Surface	fresh water			8 5/8	216'	none
line and shale				5 1/2 "	3645	2375

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set. Spotted 85 foot of sand from plug back T.D. of 3534. Then spotted 5 sacks cement on top of sand. Shot 5 1/2" casing off at 2375' from surface. Pumped 3 sacks Hulls then 15 sacks gel then 3 sacks Hulls Pumped 90 sacks cement 50/50 poz with 8% gel then 10 sacks of gel. Released plug. Pumped 50 sacks cement. Well Plugged. 9-11-84 at 2.45p.m.

RECEIVED
 STATE CORPORATION COMMISSION
10/22/84
 OCT 22 1984

CONSERVATION DIVISION
 Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
 Name of Plugging Contractor Halliburton

STATE OF Kansas COUNTY OF Rooks, ss.

Thomas E. Brown (owner ~~ZZZZZZZZZZ~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Thomas E. Brown
 407 S. Main, Plainville, Kansas 67663
 (Address)

SUBSCRIBED AND SWORN TO before me this 19th day of October, 1984

Kathy A. Wise
 Notary Public.

My Commission expires: 5-27-86

