

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

WELL PLUGGING RECORD

Rooks County. Sec. 20 Twp. 9S Rge. 18 (W)

Location as "NE/CNW/SW" or footage from lines SE NE SE

Lease Owner Heathman-Seeligson Drilling Co.

Lease Name Baumgartner 'C' Well No. 2

Office Address 254 No. Washington

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 8-14 19 54

Application for plugging filed 8-14 19 54

Application for plugging approved 8-14 19 54

Plugging commenced 8-14 19 54

Plugging completed 8-14 19 54

Reason for abandonment of well or producing formation Dry Hole Abandoned - well running structurally low compared to wells & dry holes in area.

If a producing well is abandoned, date of last production --- 19 ---

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Box 326, Hays, Kansas

Producing formation none Depth to top --- Bottom --- Total Depth of Well 3120 Feet

Show depth and thickness of all water, oil and gas formations.


OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				4 Jts. 8 5/8" Spiralweld casing.	160'	none
				cemented w/100 sacks cement & 1 sack Cal. Shlerride		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Stirred pits. Filled hole with heavy mud. Set plug @ 155' with 1/2 sacks Hull and 15 sacks cement. Set top plug @ 40' with 1/2 sacks Hulls and 10 sacks cement.



(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Heathman-Seeligson Drilling Co.  
Address 254 No. Washington, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss. H. D. Shreve (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. HEATHMAN-SEELIGSON DRILLING CO.

(Signature) By: [Signature]  
254 No. Washington, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 16 day of August, 19 54

My commission expires June 28, 1956 D. Marjorie Mott Notary Public.

PLUGGING  
FILE SEC 20 T 9 R 18 W  
BOOK PAGE 56 LINE 39

DRILLERS' LOG

NAME: BAUMGARTNER 'C' #2 DATE SPUNDED: 8-9-54  
 LOCATION: SE NE SE Sec. 20-9E-18W ROTARY COMPLETED: 8-14-54  
 Rocks County, Kansas  
 OPERATOR: Heathman-Seeligson Drilling Co. ELEVATION: 2164 Gr  
 CONTRACTOR: Heathman-Seeligson Drilling Co. 2167 Df  
 2169 KB  
 SURFACE CASING: 4 Jts. 8 5/8" Spiralweld casing ROTARY T.D.: 3120'  
 set @ 160' w/100 sacks cement  
 and 1 sack Cal. Chloride. Cement  
 Circulated.  
 OIL STRING: none run - Dry and abandoned at RTD

GEOLOGICAL TOPS (KB)

Anhydrite 1496 ( # 673 )  
 Topeka 3107 ) - 938 )  
 Total Depth 3120 ( - 951 )


LOG

(Figures indicate bottom of formation)

Clay and Sand	0 to 40
Shale	160
Shale, Sand and Shells	1016
Sand	1220
Red Bed and Shale	1490
Shale & Shells	1496
Anhydrite	1538
Shale and Shells	2055
Shale and Lime Shells	2225
Lime and Shale	3120
R.T.D.	3120

The undersigned, H. D. SHREVE, hereby certifies that the above log is a true and correct log of the formations encountered in drilling the above noted well as reflected by the Daily Drilling Reports.

HEATHMAN-SEELIGSON DRILLING CO.

By: 

Subscribed and sworn to before me  
 this 16th day of August 1954.

D. Marjorie Mott  
 Notary Public

My Commission expires: June 28, 1956

RECEIVED  
 STATE CORPORATION COMMISSION  
 AUG 27 1954  
 CONSERVATION DIVISION  
 Wichita, Kansas

**PLUGGING**  
 FILE SEC 20 T 9 R 18W  
 BOOK PAGE 56 LINE 39