

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Quinque Oil & Gas Producing Co.
Address: PO Box 710 Liberal KS 67905-0710
Phone: (620)624-2578 Operator License #: 33320
Type of Well: Gas Oil KCC Pkt Peroper - Mike
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) Docket #: 212107
(If SWD or ENHR)
The plugging proposal was approved on: 1-25-07 (Date)
by: Eric MacClarín (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)

API Number: 15-189-20364-0000
Lease Name: Lilly Nelson
Well Number: 1
Spot Location (QQQQ): SW-SW-SW-NE
2481 Feet from North / South Section Line
2532 Feet from East / West Section Line
Sec. 1 Twp. 33 S. R. 35 East West
County: Stevens
Date Well Completed: 11-16-77
Plugging Commenced: 1-25-07
Plugging Completed: 1-29-07

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				9 5/8	1685	—
				7	6499	1220


Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Mixed 500 lb. hulls & 40 sx cmt. to plug perfs from 6122 to 5922, 7 was stuck inside 9 5/8 @ 1300. Shot loose @ 1220.
Circ. hole w/mud & mixed 75 sx plug 1220 to 1020
50 sx 600 to 500 12 sx 40 to 0 Capped 9 5/8 3 ft below G.L.

Name of Plugging Contractor: SARGENT AND HORTON PLUGGING, INC. License #: 31151
Address: Rt. 1, Box 49 BA Tyrone, OK 73951-9731
Name of Party Responsible for Plugging Fees: ROGER CLINE Quinque Oil & Gas Production Co
State of KANSAS County, SEWARD, ss. KCC Pkt Peroper - Mike
OPERATOR (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]
(Address) MICHAEL MOORE, PRES QUINQUE OIL & GAS PRODUCING Co
120 BOX 710 LIBERAL KS 67905



SUBSCRIBED and SWORN TO before me this 15th day of February, 2007
Patricia L. Sizemore, PCS My Commission Expires: April 12, 2009
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PPT