

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-189-20364-00-00
Spot: SWSWNE Sec/Twnshp/Rge: 1-33S-35W
2481 feet from N Section Line, 2532 feet from E Section Line
Lease Name: LILLY NELSON Well #: 1
County: STEVENS Total Vertical Depth: 6500 feet

Operator License No.: 33320
Op Name: QUINQUE OIL & GAS PRODUCING CO
Address: PO BOX 710
LIBERAL, KS 67905

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	7	6499	1220	WITH 300 SX CMT
SURF	9.625	1685		WITH 650 SX CMT #211.25

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/25/2007 1:00 PM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: JOHN Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: PUMP 500# HULLS & 40 SX CMT. PLUG AT 1710' WITH 75 SX CMT. PLUG AT 600' WITH 50 SX CMT. PLUG AT 40' WITH 12 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/29/2007 1:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

7" CASING WAS NOT FREE BELOW 1220'. PUMP 400# HULLS & 40 SX CMT TO 6128'. DISPLACE WITH MUD. PRESSURE TO 900# & HELD. 1ST PLUG AT 1220' WITH 75 SX CMT. 2ND PLUG AT 600' WITH 50 SX CMT. 3RD PLUG AT 80'-0' WITH 12 SX CMT. GOOD CIRCULATION.

Perfs:


INVOICED
DATE 2-19-07
INV. NO. 2007061365

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 15 2007
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED COMMON CEMENT BY SARGENTS.

Plugged through: CSG

District: 01



Signed

Ken Jehlik

(TECHNICIAN)

Form CP-23

PK