

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-001-01892-00-01
Spot: NENWNW Sec/Twnshp/Rge: 2-25S-17E
5134 feet from S Section Line, 4271 feet from E Section Line
Lease Name: PIQUA GAS STORAGE Well #: 6
County: ALLEN Total Vertical Depth: 900 feet

Operator License No.: 33097

Op Name: SOUTHERN STAR CENTRAL GAS PIPE

Address: 4700 HIGHWAY 56
OWENSBORO, KY 42301

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.178	864	0	154 SX
SURF	8.25	8	0	

\$ 35.00

Well Type: GWI

UIC Docket No:

Date/Time to Plug: 11/22/2006 8:00 AM

Plug Co. License No.: 32006

Plug Co. Name: HURRICANE WELL SERVICE, INC.

Proposal Rcvd. from: BERNIE ROCKERS

Company: SOUTHERN STAR CENTRAL GAS P Phone: (785) 448-4816

Proposed Plugging Method: CLEAN OUT TO T.D. PLUG SOLID WITH CLASS A CEMENT. CUT CASING 4' BELOW SURFACE. BACKFILL AND RECLAIN SITE.

Method:

Plugging Proposal Received By: CLAYTON TITEL

WitnessType: PARTIAL

Date/Time Plugging Completed: 11/22/2006 5:00 PM

KCC Agent: CLAYTON TITEL

Actual Plugging Report:

THIS WELL CONSISTED OF 5" CASING TO 864' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. TO PLUG THE WELL 2" TUBING WAS RAN INTO THE WELL TO T.D.. CEMENT WAS PUMPED INTO THE 2" TUBING UNTIL CEMENT CIRCULATED FROM THE CASING AT SURFACE. THE WELL WAS THEN SHUT IN.

Perfs:

RECEIVED
KCC DISTRICT #3
FEB 7 2007 CPT
CHANUTE, KS

INVOICED
DATE 2-19-07
INV. NO. 200 2061369

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 15 2007
CONSERVATION DIVISION
WICHITA, KS

Remarks:

Plugged through: TBG

District: 03

Signed Clayton P. Titel
(TECHNICIAN)