

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-055-00008-00-00  
Spot: C Sec/Twnshp/Rge: 15-22S-31W  
2640 feet from S Section Line, 2640 feet from E Section Line  
Lease Name: MEARIS Well #: 1  
County: FINNEY Total Vertical Depth: 2758 feet

Operator License No.: 32787  
Op Name: KANSAS NATURAL GAS OPERATING, I  
Address: PO BOX 818 1200 MAIN STREET  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		1316		\$ 89.64
CIBP		2650		
PROD	5.5	2758	0	
SURF	8.625	286		

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/19/2006 12:30 PM  
Plug Co. License No.: 99997 Plug Co. Name: HALLIBURTON ENERGY SERVICES  
Proposal Rcvd. from: STEVE LEHNING Company: KANSAS NATURAL GAS Phone: (620) 675-8185

Proposed Plugging Method: SET CAST IRON PLUG AT 2650'+ OR -. DUMP 2 SACKS CEMENT ON TOP OF PLUG. PRESSURE TEST CASING FOR INTEGRITY. SPOT 20 SACKS PLUG OF 60/20 POZMIX AT 2150' THRU TUBING. MOVE UP HOLE TO 1800' AND SET 25 SACKS PLUG. MOVE UP HOLE TO 1400' AND SET 25 SACK PLUG. PERFORATE 5 1/2" CASING @ 300' TO EST. CIRCULATION AND FILL 5 1/2" AND ANNULUS FROM 300' TO SURFACE. HOOK ONTO BACKSIDE AND TRY TO PUMP 75 SACKS OVER CASING CAPACITY. CUT OFF 6' BELOW GROUND AND WELD CAP & BACKFILL. TOTAL CEMENT APPRX. 300 SACKS. KCC: JIM HOLLAND.

Plugging Proposal Received By: \_\_\_\_\_ WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 01/23/2007 2:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

12/19/06: CIBP @ 2650'. CIBP @ 1316'. PERFORATE AT 1250'. 01/23/07: PUMP 70 SX CMT, 200# HULLS, & 91 SX CMT. PRESSURED TO 500# & HELD. NO BLOW OR CIRCULATION UP ANNULUS. HOOK UP TO 5 1/2" X 8 5/8" ANNULUS & PUMP 10 SX CMT WELL PRESSURED TO 50#. (ONLY PRESSURED TO 50# DUE TO PUMP PROBLEMS).

Perfs:

Top	Bot	Thru	Comments
2692	2710		HERRINGTON

**INVOICED**  
DATE 2-19-07  
INV. NO. 2007061361


**RECEIVED**  
KANSAS CORPORATION COMMISSION  
FEB 15 2007

Remarks: USED 60/40 POZMIX 6% GEL 2% CC 1/4# FLO SEAL BY HALLIBURTON.

CONSERVATION DIVISION  
WICHITA, KS

Plugged through: CSG

District: 01



Signed Ken Jehlik  
(TECHNICIAN)

Form C  
*PKT*