

4-070096

API NO. 15-163-015740000

5-20

Received  
KANSAS CORP CO  
5/27/98  
MAY 27 1998

API Number: 15- - 3-23-47

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

NW NW NE /4 SEC. 28, 09 S, 18 W  
4950 feet from S section line  
2310 feet from E section line

KCC 2AP  
Ernest S.

Operator license# 6627

Lease: Rempe Well # 1

Operator: Prospect Oil & Gas

County: Rooks 116.91

Address: P.O. Box 837  
Russell, Kansas 67665

Well total depth 3597 feet  
Conductor Pipe: 0 inch @ 0 sxs.  
Surface pipe 8 5/8 Inch @ 1496 feet  
W/625 sxs.

ABAND. oil well , Gas well \_\_\_\_\_, Input well \_\_\_\_\_, SWD. \_\_\_\_\_, D&A \_\_\_\_\_

Plugging contractor: Prospect Oil & Gas License# 6627

Address: P.O. Box 837 - Russell, Kansas 67665

Company to plug at: Hour: 1:00 P.M. Day: 20 Month: May Year: 1998

Plugging proposal received from: Larry Schaffer

Company: Prospect Oil & Gas Phone: 785-483-6266

Were: 8 5/8" set at 1496' cwc 625 sxs. 5 1/2" set at 3595' w/75 sxs.  
Packer and tubing stuck in hole at 1150'. Hole in 5 1/2" casing approximately 1120' - 1150'.  
Ordered 350 sxs 60/40 pozmix - 10% gel with 600# hulls.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All  , Part [ ] , None [ ]

Completed: Hour: 5:30 P.M. , Day: 20 , Month: May , Year: 1998

Actual plugging report: Allied pumped 50 sxs w/100# hulls down tubing. Shot tubing off at 1100', cwc with 120 sxs and 400# hulls. P.T.O.H. Pumped 180 sxs down 5 1/2" casing - good circulation on backside. Ran out of cement. Max. 400# with zero S.I.P.  
05-21-98 - Pumped 10 sxs down backside. Max. P.S.I. 1000#. S.I.P. 800#.  
Topped off 5 1/2" casing with 25 sxs. Stayed full.

Remarks: Company man left location on 05-20-98, after tubing shot off.

Condition of casing(in hole): GOOD \_\_\_\_\_ BAD  Anhy.plug: YES  NO \_\_\_\_\_

Bottom plug(in place): YES \_\_\_\_\_, CALC \_\_\_\_\_, NO \_\_\_\_\_ Dakota plug: YES  , NO \_\_\_\_\_

Plugged through TUBING  , CASING \_\_\_\_\_ Elevation: 2165 GL

I did  / did not [ ] observe the plugging.

*Richard Williams*  
(agent)

Form CP-2/3

**INVOICED**

DATE MAY 27 1998

INV. NO. 50636

5-20 SEP 18 1998