

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-01573-00-01

Spot: SWNESE

Sec/Twnshp/Rge: 28-9S-18W

1650 feet from S Section Line, 990 feet from E Section Line

Lease/Unit Name: S PARADISE CREEK

Well Number: 302

County: ROOKS

Total Vertical Depth: 3582 feet

Operator License No.: 5399

Production Casing Size: 5.5 feet: 3579 UNKNOWN

Op Name: AMERICAN ENERGIES CORPORATION

Surface Casing Size: 8.625 feet: 185 UNKNOWN

Address: 155 N. MARKET, STE 710
WICHITA, KS 67202

42
\$116

Well Type: EOR

UIC Docket No: E15855.2

Date/Time to Plug: 06/24/2003 10:00 AM

Plug Co. License No.: 99998

Plug Co. Name: COMPANY TOOLS

Proposal Rcvd. from: LAWRENCE W. JACKSON Company: AMERICAN ENERGIES CORPORAT Phone: (620) 793-2146

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 10% gel - 500# hulls.
Perf casing at 1975' - 1495' - 925'.

Plugging Proposal Received By: HERB DEINES

WitnessType: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 06/25/2003 4:30 PM

KCC Agent: DENNIS HAMEL

Actual Plugging Report:

RIH with tubing to 2000'+.
Spotted 80 sxs cement with 200# hulls.
Pulled tubing to 1000'.
Spotted 100 sxs cement with 200# hulls in cement - circulated at surface.
POOH with tubing.
Squeezed casing with 50 sxs cement.
Max. P.S.I. 500#. S.I.P. 200#.
Squeezed 8 5/8" S.P. with 50 sxs cement plus 100# hulls.
Max. P.S.I. 200#. S.I.P. 100#.

RECEIVED
8/13/03
AUG 13 2003
KCC WICHITA

Remarks: LEASE ALSO KNOWN AS HAYES #2. ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

Dennis L Hamel
(TECHNICIAN)

INVOICED

8-13-03
2004060391

JUL 28 2003

Lowell Drilling Co. #2 Hayes

28-9-18W
SW NE SE

Contr. Lowell Drilling Co.

No API
Hooks

County

E2154 Comm 3-19-47 Comp 10-24-47 IP 195 BOPD & 45% WTR

Tops	Depth	Datum	Casing
			8" 185 Dst 3361-68, open 1/2 hr,
ANE	1195		5" 3579 Rec 15' mud
TOP	3061		Dst 3398-3410, open 1 hr,
HEEB	3277		Rec 40' oil & 60' oil
			cut mud & 235' wtr
LANS	3320		Acid 500 & 1500; Swb 6
			BOPH/6 hrs; PB 3447
			Perf 27 S-3409-15; Acid
ARB	3579		1000; Perf 22 S-3369-73
			Acid 1000; Swb 30 BPH,
T. D.	3582		25% wtr/6 hrs

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

