

4-070157

15-163-01572-00-00

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15- - 1947

NE NE SE /4 SEC. 28, 09 S, 18 W
2310 feet from S section line
330 feet from E section line

(Paradise Creek)

Operator license# 8363

Lease: Hayes Well # 1

Operator: Glass Oil Company

County: Rooks

Address: P.O. Box 52890
Tulsa, OK 74152

Well total depth 3592 feet
Conductor Pipe: 0 inch @ 0 sxs.
Surface pipe 8 5/8 Inch @ 185 feet
W/100 sxs.

ABAND. oil well , Gas well , Input well , SWD. , D&A

Plugging contractor: Glass Oil Company License# 8363

Address: P.O. Box 52890 - Tulsa, OK 74152

Company to plug at: Hour: 1:00 P.M. Day: 2 Month: December Year: 1999

Plugging proposal received from: Gene Glass

Company: Glass Oil Company Phone: 918-747-9919

Were: 5 1/2" set at unknown. No records. Cast iron plug set above top of arbuckle.
Prod. Perfs 3325' - 3415'. PBDT 3440'.
Ordered out 350 sxs 60/40 pozmix 10% gel with 600# hulls.
Squeeze salt section 1993' with 225 sxs 2695'.
Dakota 632' - 932'.
Anhydrite 1490' - 1520'.
Salt 1812' - 1930'.

Plugging Proposal Received by: Rich Williams

Plugging operations attended by agent? All , Part , None

Completed: Hour: P.M. Day: 2, Month: December, Year: 1999

Actual plugging report: Dug out surface pipe, casing support hanger. No head.
Welder orange peeled surface pipe to 5 1/2" with 2" collar welded in it.
Allied pumped 35 sxs 60/40 pozmix - 10% gel with 100# hulls down backside.
Max. P.S.I. 500#. S.I.P. 200#. Ran 2 7/8" tubing to 2500'. Allied pumped 100 sxs with 200# hulls down tubing (no circulation). Pulled tubing to 1900' and pumped 75 sxs cement with 100# hulls, weak circulation. Pulled to 930' and pumped 90 sxs cement with 200# hulls, circulated cement. PTOH and squeezed 10 sxs. No pressure - hole stayed full.
12-03-99 - Allied found top cement at 171' from surface. Topped off with 20 sxs cement.

Remarks:
Condition of casing(in hole): GOOD BAD Anhy.plug: YES NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO
Plugged through TUBING , CASING . Elevation: 2155 GL

I did / did not observe the plugging.

INVOICED

DATE 12/21/99

INV. NO. 60982

Richard Williams
KANSAS CORPORATION COMMISSION
Form CP-2/3

DEC 17 1999
12/17/99
CONSERVATION DIVISION
WICHITA, KS

R