

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-01547-00-00  
Spot: SWNENE Sec/Twnshp/Rge: 20-9S-18W  
4290 feet from S Section Line, 1650 feet from E Section Line  
Lease/Unit Name: BAUMGARTNER B Well Number: 4  
County: ROOKS Total Vertical Depth: 3591 feet

Operator License No.: 101

Production Casing Size: 5.5 feet: 3582

Op Name: KCC FEE FUND

Surface Casing Size: 8.625 feet: 151

Address: 130 S. MARKET, ROOM 2078  
WICHITA, KS 67202

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 06/20/2003 4:30 PM

Plug Co. License No.: 6901

Plug Co. Name: D S & W WELL SERVICING, INC.

Proposal Rcvd. from: JOE STRUBE

Company: D S & W WELL SERVICING, INC.

Phone: (620) 587-3361

Proposed Plugging Method: Ordered out 470 sxs 60/40 pozmix - 10% gel.

Plugging Proposal Received By: JAY PFEIFER

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 06/20/2003 7:30 PM

KCC Agent: JAY PFEIFER

**Actual Plugging Report:**

Washed well down to 1500' and hit hard bridge.  
Perforated casing at 800' and 1425'.  
TIH with tubing to 1470' - mixed and pumped 120 sxs cement.  
Pulled up to 770' and circulated cement up 8 5/8" and 5 1/2" with 150 wxs cement.  
POOH. Swaged onto 5 1/2" - pumped 200 sxs cement.  
S.I.P. 150#.

Remarks: COPELAND ACID AND CEMENTING.

Plugged through: TBG


District: 04

RECEIVED

JUL 01 2003

KCC WICHITA

Signed



(TECHNICIAN)



JUN 25 2003

HEATHMAN-SEELIGSON

#4

BAUMGARTNER 'B' SW NE NE

20-9-18W


Contr. \_\_\_\_\_ ROOKS County

E 2175 RB Comm. \_\_\_\_\_ Comp. 2-26-54 IP 2074 BOPD  
DRAW DOWN

Tops	Depth	Datum
ANH	1504	671
TOP	3088	-913
HEEB	3298	-1123
TOR	3318	-1143
LANS	3338	-1163
ARB	3580	-1405
TD	3591	-1416

Casing  
 8" 151 DST 3419-32/1 HR, 30'  
 5" 3582 OCM, 90' OC MDY WTR  
 BHP 1.200#  
 DP: COTB: DD 3585: SO: DD 3588  
 SWB 3 BOPH/2 HR: DD 3591: SWB  
 6 BOPH: ACID 500: SWB 42 BOPH  
 1 HR

PARADISE CREEK WEST POOL



INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS




Photo 5/22/02