

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-01546-00-00  
Spot: NENWNE Sec/Twnshp/Rge: 20-9S-18W  
4950 feet from S Section Line, 1650 feet from E Section Line  
Lease/Unit Name: BAUMGARTNER Well Number: 2  
County: ROOKS Total Vertical Depth: 3590 feet

Operator License No.: 101

Production Casing Size: 5.5 feet: 3585

Op Name: KCC FEE FUND

Surface Casing Size: 8.625 feet: 164

Address: 130 S. MARKET, ROOM 2078  
WICHITA, KS 67202

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 06/20/2003 10:00 AM

Plug Co. License No.: 6901

Plug Co. Name: D S & W WELL SERVICING, INC.

Proposal Rcvd. from: JOE STRUBE

Company: D S & W WELL SERVICING, INC.

Phone: (620) 587-3361

Proposed Plugging Method: Ordered out 475 sxs 60/40 pozmix - 10% gel.

Plugging Proposal Received By: JAY PFEIFER

WitnessType: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 06/20/2003 4:30 PM

KCC Agent: JAY PFEIFER

**Actual Plugging Report:**


Washed well down to 1020'.  
Hole started to catch tubing - decided to P&A.  
Perforated casing at 800'.  
TIH with tubing to 1000' and circulated cement with 250 sxs cement.  
POOH. Topped with 50 sxs cement.  
Hooked up to annulus and pumped 175 sxs cement with 400# hulls.

Remarks: COPELAND ACID AND CEMENTING.

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

RECEIVED

JUL 01 2003

KCC WICHITA

JUN 25 2003

HEATHMAN-SEELIGSON #2 BAUMGARTNER 20-9-18W NE NW NE

Contr. HEATHMAN-SEELIGSON ROOKS County

E 2172 o.B. Comm. Comp. 1-29-51 IP 3000 BOPD DRAW DOWN

Tops	Depth	Datum
ANH	1505	667
TOP	3092	-920
HEEB	3302	-1130
TOR	3322	-1150
LANS	3312	-1170
ARR	3582	-1110
TD	3590	-1118

Casing  
 8" 164 DST 3331-66/1 HR; 135'  
 5" 3585 MPY SLT WTR, BHP 920#  
 DST 3495-3545/1 HR, 60'  
 WTR, 220' 0 & WTR CM;  
 BHP 1155#  
 DP: COTB: BAIL 1 BOPH: DD  
 3590: BAIL 10 1/2 BOPH: ACID 500  
 SWB 38 BOPH/2 HR

PARADISE CREEK WEST POOL


INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS

Couldnt get Top off  
 Fluid @ ?  
 Photo 1/3/03

