

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-21831-00-00
Spot: SWSWSW Sec/Twnshp/Rge: 25-19S-11W
317 feet from S Section Line, 5082 feet from E Section Line
Lease Name: ISERN Well #: 1
County: BARTON Total Vertical Depth: 3298 feet

Operator License No.: 31714
Op Name: NOVY OIL & GAS, INC.
Address: 125 N. MARKET STE. 1230
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3295	0	w/50 sxs cmt
SURF	8.625	212	0	w/unknown sxs cmt

\$ 107.19

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/09/2007 2:30 PM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: ED NEMNICH Company: D S & W WELL SERVICING, INC. Phone: (620) 587-3361

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 10% gel - 500# hulls.
Top of fish 1077' 4 1/2" casing to TD - Pulled 1077' of 4 1/2". Attempted to fish casing with no success.
Hole filled with heavy return mud.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/09/2007 2:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

RIH with tubing to 1037' - could not get down. Rigged to tubing - pumped 50 sxs neat, followed with 75 sxs cement with 300# hulls mixed in.
Pulled tubing to 575'. Rigged to tubing - pumped 25 sxs cement with 100# hulls mixed in.
Pulled tubing to 225'. Rigged to tubing - pumped 40 sxs cement with 100# hulls mixed in.
Pulled tubing to 40'. Rigged to tubing - pumped 10 sxs cement to circulate cement to surface.
Hole standing full.

Perfs:

INVOICED
DATE 3-1-07
INV. NO. 2007061418

RECEIVED
FEB 28 2007
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #26363.

Plugged through: TBG

District: 04

Signed

[Signature]
(TECHNICIAN)
BOB

Form CP-2/3

FEB 12 2007

PVT

MIDWAY DRILLING INC

P.O. BOX 1325

#1 ISERN

25-19-11W

GREAT BEND, KS 67530

SW SW SW

CONTR ALLEN DRILLING

CTY BARTON

GEOL

FIELD CHASE-SILICA

E 1773 KB CM 2/1/80 CARD ISSUED 8/28/80 IF P 14 BOPD & WTR

API 15-009-21,831

ARB OH 3295-98

SMP	TOPS	DEPTH	DATUM
TOP	2614	- 841	
HEEB	2882	-1109	
TOR	2901	-1128	
DOUG	2911	-1138	
BR LM	3002	-1229	
KC	3025	-1252	
ARB	3295	-1522	
RTD	3297	-1524	
DDTD	3298	-1525	

8-5/8" 212, 4 1/2" 3295/50sx

DST (1) 3006-3060 (LKC)/30-30-30-30,
 205' GIP, REC 490' GCM, 63' GCWM,
 SIP 739-754#, EP 30-103/113-164#,
 MICT - CO, (ARB OH), DD 3298 TD, SWB
 10 BFPH, 12% O, NAT, POP

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS