

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - 119-21176-0000 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date: 1/28/2007

Well Operator: Keith F. Walker Oil & Gas Company, L.L.C. KCC License #: 33392
(Owner/Company Name) (Operator's)

Address: 103 West Boyd Street City: Norman

State: OK Zip Code: 73069 Contact Phone: (405) 701 - 0676

Lease: Razorhawk Well #: 35 #1 Sec. 35 Twp. 31S S. R. 27 East West

C - SE - NW Spot Location / QQQQ County: Meade

1980 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

1980 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: 20" Set at: 60' Cemented with: 200 Sacks

Surface Casing Size: 8 5/8" Set at: 1449 Cemented with: 970 Sacks

Production Casing Size: None Set at: _____ Cemented with: _____ Sacks

List (ALL) Perforations and Bridgeplug Sets: None

Elevation: 2525.4 (G.L. / K.B.) T.D.: 5800' PBTD: _____ Anhydrite Depth: _____
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): 1st Cement Plug at 1473' with 50 sx Class C 60/40 Poz mix with 6% gel.
Set 2nd Cement Plug at 637' with 40 sx of Class C 60/40 Poz with 6% gel. Set 3rd and Final Plug at 60' to Surface with 20 sx
of Class C 60/40 Poz with 6% gel. Plug Rat and Mouse Holes with 20 sx of Class C 60/40 with 6% gel.

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? Please find the ACO-1 attached.

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Barry Jones, Drilling Supervisor

Phone: (405) 834 - 2319

Address: 103 West Boyd Street- Norman, OK 73069 City / State: Norman, OK

Plugging Contractor: Matiburton Energy Services Titaw Drilling KCC License #: 5287 33630
(Company Name) (Contractor's)

Address: 110 East Pancake Boulevard- Liberal, KS 67901 Phone: (620) 624 - 3879

Proposed Date and Hour of Plugging (if known?): 2/11/2007

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 2/12/2007 Authorized Operator / Agent: Alma [Signature]
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

* Well already plugged - KCC-DIG

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 15 2007
CONSERVATION DIVISION
WICHITA, KS