

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: BEREN, CORP.  
Address: PO BOX 723 HAYS, KS 67206  
Phone: (785) 628-6101 Operator License #: 5364  
Type of Well: GAS Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: 2-7-07 (Date)  
by: Case Morris (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-009-16601-00-01  
Lease Name: BIRD A OWWO *KCC PPT per RBDMS 2-26-07*  
Well Number: K1  
Spot Location (QQQQ): C - SE AW SE  
1338 Feet from  North /  South Section Line  
1409 Feet from  East /  West Section Line *KCC PPT per RBDMS*  
Sec. 28 Twp. 18 S. R. 15  East  West *GPS*  
County: BARTON  
Date Well Completed: 5-15-76  
Plugging Commenced: 2-7-07  
Plugging Completed: 2-9-07

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		0	908'	8-5/8	5-15-76	---
		0	3466'	5-1/2	5-15-76	----

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

RIG UP PUMP STUCK SHUT DOWN, STRIP WELL OUT, ROD & TBG SENT TO ICO. RIG UP PERF-TECH AND SHOT 2 HOLES AT 400' AND 900'  
PER KCC. TIH W/ 85 JTS 2-3/8 BX W-STRING PUMP 100 SKS W/ 300# HULLS AT 3800', PULL TO 1400' AND PUMP 125 SKS  
W/ 100# HULLS, CIRC CMT TO SURFACE. TOH AND PUT 50 SKS DOWN ANN AND 200 SKS DOWN CSG CMT DID CIRC W/ ANNULUS  
TOTAL 275 SKS 60/40 10% GEL 400# HULLS

Name of Plugging Contractor: H-D OILFIELD SERVICE *Beren Corporation* License #: 32970 *5364* *per RBDMS PPT KCC*  
Address: PO BOX 87 BAZINE, KS 67516  
Name of Party Responsible for Plugging Fees: Mark Leiker *per RBDMS*  
State of KS County, ELLIS, ss.

\_\_\_\_\_  
(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Mark Leiker

(Address) PO BOX 723 HAYS, KS 67601



SUBSCRIBED and SWORN TO before me this 19 day of FEBRUARY 20 07  
Shanna Miller My Commission Expires: 9/19/09  
Notary Public



FEB 21 2007

*PPT*