

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: VESS OIL CORPORATION
Address: 1700 Waterfront Parkway, Bldg. 500 Wichita, KS 67206
Phone: (316) 682-1537 Operator License #: 5030
Type of Well: oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 1/18/07 (Date)
by: Duane Krueger (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Admire 550 Depth to Top: 534 Bottom: 544 T.D. 750
Admire 650 Depth to Top: 649 Bottom: 659 T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 015-23,475 - 00 - 00
Lease Name: Burlingame-Stokes
Well Number: #79
Spot Location (QQQQ): AW - ~~NE~~ - NE - SW
2000' 1986 Feet from North / South Section Line
2050' 3351 Feet from East / West Section Line
Sec. 28 Twp. 25S S. R. 05E East West
County: Butler
Date Well Completed: 9/11/96
Plugging Commenced: 2/1/07
Plugging Completed: 2/1/07

KCC
PCT
Per
GPS.

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Admire 550	sli oil & sw	534'	544'	8-5/8"	212'	none
Admire 650	sli oil & sw	649'	659'	5-1/2"	745'	none

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

CIBP already set @ 628'. Run tubing to 603'. Circulate hole. Mix and pump 54 sx. Circulate hole full. Pull out.
Tie onto 5-1/2" and pressure cement up with 7 sx. Witnessed by Duane Krueger.
United Ticket #7662 - 60/40 pozmix, 4% gel


Name of Plugging Contractor: United Cementing and Acid Company, Inc. License #: 30437
Address: 2510 W. 6th, El Dorado, KS 67042

Name of Party Responsible for Plugging Fees: Vess Oil Corporation
State of Kansas County, Sedgwick, ss.

Casey Coats (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Casey Coats
(Address) 8100 E. 22nd Street North, Bldg. 300, Wichita, KS 67226

SUBSCRIBED and SWORN TO before me this 2nd day of February 20 07
Michele Henning My Commission Expires: _____
Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PCT



United Cementing and Acid Co., Inc.

Oil Well Cementing & Acidizing
 (316) 321-4680 • 800-794-0187 • FAX (316) 321-4720
 2510 West 6th Street • El Dorado, KS 67042

8122

SERVICE TICKET

✓ 7662

DATE 2-01-07

COUNTY Butler CITY _____

CHARGE TO Vess oil corp.

ADDRESS _____ CITY _____ ST _____ ZIP _____

LEASE & WELL NO. B-310kas - 779 CONTRACTOR Simmons Well Serv.

KIND OF JOB plug SEC. _____ TWP. _____ RNG. _____

DIR. TO LOC. _____ OLD NEW

Quantity	MATERIAL USED	Serv. Charge
70 SK	60/40 4% 12 @ 10.85	
3 SK	gel @ 11.00	
1 SK	C.S. @ 2.50	
74	BULK CHARGE	
	BULK TRK. MILES <u>min chg</u>	125.00
2.5	PUMP TRK. MILES	
	PLUGS	
		.0530 SALES TAX
		TOTAL

T.D. _____

CSG. SET AT _____ VOLUME _____

SIZE HOLE 5 1/2

TBG SET AT _____ VOLUME _____

MAX. PRESS. _____

SIZE PIPE 2 3/8

PLUG DEPTH _____

PKER DEPTH _____

PLUG USED _____

TIME ON LOCATION 8:30 AM TIME FINISHED 10:00 AM

REMARKS: Mixed 9 BBLs cement down 2 3/8 tubing circulated cement from 603 To surface Puled tubing Tied on to 5 1/2 mixed 1 BBL cement Pressured up to 500' shut in at 250 #

EQUIPMENT USED

NAME UNIT NO. NAME
Shawn Scobee
Jeff Shell P-15
 CEMENTER OR TREATER

RECEIVED NO. KANSAS CORPORATION COMMISSION
Darren Bernauer
B-3
FEB 21 2007
 CONSERVATION DIVISION
 OWNER'S REP. WICHITA, KS