

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: VESS OIL CORPORATION  
Address: 1700 Waterfront Parkway, Bldg. 500 Wichita, KS 67206  
Phone: (316) 682-1537 Operator License #: 5030  
Type of Well: oil Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: 1/18/07 (Date)  
by: Duane Krueger (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
Admire 550 Depth to Top: 554 Bottom: 558 T.D. 730  
Admire 650 Depth to Top: 670 Bottom: 682 T.D. \_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-015-21,649-00-00  
Lease Name: Atkins A  
Well Number: #2  
Spot Location (QQQQ): \_\_\_\_\_ - NW - SE - NE  
1650' Feet from  North /  South Section Line  
990' Feet from  East /  West Section Line  
Sec. 29 Twp. 25S S. R. 05E  East  West  
County: Butler  
Date Well Completed: 9/10/81  
Plugging Commenced: 1/31/07  
Plugging Completed: 2/1/07

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Admire 550	sli oil & sw	554'	558'	8-5/8"	48	none
Admire 650	sli oil & sw	670'	682'	5-1/2"	725	none

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.


1/31/07 - Tbg set below 650' perfs @ 690'. Mix and pump 84 sx cement. Circulate hole full. Pull tubing.  
Tie onto 5-1/2" and pressure cement away with 14 sx. Holding 500 psi. United Ticket #7661  
60/40 pozmix, 4% gel 2/1/07 - Run 1" tbg inside 5-1/2" & 8-5/8" annulus, tag cement @ 36'. Pick up 1'  
Mix and pump 14 sx, cement circulated. Both days witnessed by Duane Krueger

Name of Plugging Contractor: United Cementing and Acid Company, Inc. License #: 30437  
Address: 2510 W. 6th, El Dorado, KS 67042  
Name of Party Responsible for Plugging Fees: Vess Oil Corporation  
State of Kansas County, Sedgwick, ss. \_\_\_\_\_  
Casey Coats (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Casey Coats  
(Address) 8100 E. 22nd Street North, Bldg. 300, Wichita, KS 67226

SUBSCRIBED and SWORN TO before me this 2nd day of February 20 07  
Michelle D. Henning My Commission Expires: \_\_\_\_\_  
Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PKT



# United Cementing and Acid Co., Inc.

Oil Well Cementing & Acidizing  
 (316) 321-4680 • 800-794-0187 • FAX (316) 321-4720  
 2510 West 6th Street • El Dorado, KS 67042

8119

## SERVICE TICKET

7661

DATE 1-31-07

COUNTY Barton CITY \_\_\_\_\_

CHARGE TO Vess oil corp.

ADDRESS \_\_\_\_\_ CITY \_\_\_\_\_ ST \_\_\_\_\_ ZIP \_\_\_\_\_

LEASE & WELL NO. Atkins #2 CONTRACTOR Simmons Well Serv.

KIND OF JOB Plug SEC. \_\_\_\_\_ TWP. \_\_\_\_\_ RNG. \_\_\_\_\_

DIR. TO LOC. \_\_\_\_\_  OLD  NEW

Quantity	MATERIAL USED	Serv. Charge
112 SX	60/40 4 1/2" 19 cc @ 10.25	
55 SX	gel @ 11.00	
1 SX	C.C. @ 27.50	
118	BULK CHARGE	
	BULK TRK. MILES <u>min chg</u>	155.00
2.5	PUMP TRK. MILES	n/c.
	PLUGS	
		SALES TAX
		TOTAL

T.D. \_\_\_\_\_ CSG. SET AT \_\_\_\_\_ VOLUME \_\_\_\_\_

SIZE HOLE 5 1/2 TBG SET AT \_\_\_\_\_ VOLUME \_\_\_\_\_

MAX. PRESS. \_\_\_\_\_ SIZE PIPE 2 1/2

PLUG DEPTH \_\_\_\_\_ PKER DEPTH \_\_\_\_\_

PLUG USED \_\_\_\_\_ TIME ON LOCATION 8:30 am TIME FINISHED 10:35 am

REMARKS: Tied on to 2 1/2 Tubing circulated hole clean mixed 12 BBLs cement  
Pulled tubing Tied on to 5 1/2 mixed 2 BBLs cement Displaced 1/2 BBL  
that is 250 lbs Ran 1" Down Back side @ 35 Ft cemented to surface  
Circulated cement from 670 to surface

RECEIVED  
 KANSAS CORPORATION COMMISSION

FEB 21 2007

EQUIPMENT USED		UNIT NO.	
NAME	UNIT NO.	NAME	UNIT NO.
<u>Shawn Scoble</u>		<u>DAICEN Berbauer</u>	<u>15-3</u>
<u>Jeff Shell P-15</u>			
CEMENTER OR TREATER		OWNER'S REP.	