

Notice: Fill out COMPLETELY
and return to Conservation Division
at the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Novy Oil & Gas

Address: 125 N. Market #1230, Wichita, KS 67202-1712

Phone: (316) 265-4651 Operator License #: 31714

Type of Well: Oil Well Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: January 12, 2007 (Date)

by: Herb Deines (KCC District Agent's Name)

Is ACO-1 filed? ☐ Yes ☐ No If not, is well log attached? ☐ Yes ☒ No

Producing Formation(s): List All (If needed attach another sheet)

Arbuckle Depth to Top: _____ Bottom: 2347' T.D. 2347'

_____ Depth to Top: _____ Bottom: _____ T.D. _____

_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 009-14928-0002

Lease Name: Isern

Well Number: #4

Spot Location (QQQQ): SE - SW - _____

330 Feet from ☐ North / ☒ South Section Line

4290 Feet from ☒ East / ☐ West Section Line

Sec. 25 Twp. 19s S. R. 11 ☐ East ☒ West

County: Barton

Date Well Completed: 10/12/1936

Plugging Commenced: 02/07/07

Plugging Completed: 02/08/07

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Arbuckle	Surface	0'	200'	13"	200'	0'
	Production	0'	3290'	5-1/2"	3290'	2330'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

M.I.R.U. Ran in mill on bottom of tubing to try to get in tubing to plug well. Only got 47 joints - 1435'. Call to see if deep enough. Shut down for day. Pull up to 1375'. Wait on Allied Cementing. Spot 50 sacks cement with 100# hulls. Pulled up to 575' and spot 35 sacks cement with 100# hulls. Pull up to 250' and spot 40 sacks cement with 100# hulls. Pull up to 40' and circulate 20 sacks cement to surface. R.D.M.O.

Name of Plugging Contractor: D.S. & W. Well Servicing, Inc. License #: 6901


Address: P.O. Box 231, Claflin, KS 67525

Name of Party Responsible for Plugging Fees: Novy Oil & Gas

State of Kansas County, Barton, ss.

Edward S. Nemnich

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) Edward S. Nemnich

(Address) P.O. Box 231, Claflin, KS 67525

SUBSCRIBED and SWORN TO before me this 15th day of February, 20 07

Karen J. Mitchell My Commission Expires: 4/13/2010
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED

FEB 16 2007

KCC WICHITA

PT