

Notice: Fill out COMPLETELY
and return to Conservation Division
at the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Popp Operating, Inc.

Address: PO Box 187 Hoisington, Kansas 67544

Phone: (620) 786-5514 Operator License #: 32325

Type of Well: D&A Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 1/19/07 (Date)

by: Herb Deines (KCC District Agent's Name)

Is ACO-1 filed? ☒ Yes ☐ No If not, is well log attached? ☒ Yes ☐ No

Producing Formation(s): List All (If needed attach another sheet)

_____	Depth to Top: _____	Bottom: _____	T.D. _____
_____	Depth to Top: _____	Bottom: _____	T.D. _____
_____	Depth to Top: _____	Bottom: _____	T.D. _____

API Number: 15 - 167-23,404-0000

Lease Name: Michaelis "A"

Well Number: 3

Spot Location (QQQQ): 150' N - SE - SE - SE
480 Feet from ☐ North / ☒ South Section Line

330 Feet from ☒ East / ☐ West Section Line

Sec. 36 Twp. 15 S. R. 14 ☐ East ☒ West

County: Russell

Date Well Completed: 1/19/07

Plugging Commenced: 4:00 pm 1/19/07

Plugging Completed: 8:00 pm 1/19/07

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		Surface	835'	8-5/8"	835'	none

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

1st plug @ 3275' w/ 25 sx displaced w/ 52 vis mud. 2nd plug @ 875' w/ 50 sx. 3rd plug @ 400' w/ 45 sx & 4th plug @ 40' w/ 10 sx.

Plugged rathole w/ 15 sx & mouse hole w/ 10 sx. Allied plugged w/ total of 155 sx 60/40 poz 6% gel & 1/4#/sx flocel. Job completed @ 8:00 pm 1/19/07

Name of Plugging Contractor: Discovery Drilling Company, Inc. License #: 31548

Address: PO Box 763 Hays, Kansas 67601

Name of Party Responsible for Plugging Fees: Popp Operating, Inc.

State of Kansas County, Barton, ss.

Rickey Popp

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Rickey Popp

(Address) PO Box 187 Hoisington, Ks 67544


SUBSCRIBED and SWORN TO before me this 19th day of February, 2007

Jane M. Steinert My Commission Expires: 5/20/07
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

FEB 15 2007

CONSERVATION DIVISION
WICHITA, KS



RECEIVED
KANSAS CORPORATION COMMISSION