

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 30 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
September 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

151-19018-00-02

Lease Operator: Lotus Operating Co., LLC
Address: 100 S. Main Ste. 420 Wichita, Ks. 67202

API Number: 15 - (00-27995)

Lease Name: McFadden "C"

Phone: (316) 262-1077 Operator License #: 31980

Well Number: 9

Type of Well: SWD EOR KCC per RBDMS Act Docket #: E-24268
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

Spot Location (OOQQ): C - SW - NE - NW

4290 Feet from North / South Section Line

3670 Feet from East / West Section Line

The plugging proposal was approved on: _____ (Date)

Sec. 6 Twp. 27 S. R. 12 East West

by: Steve Pfiefer (KCC District Agent's Name)

County: Pratt original 9/3/85

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Date Well Completed: 9-23-64

Producing Formation(s): List All (If needed attach another sheet)

Plugging Commenced: 1-29-07 per RBDMS

Depth to Top: _____ Bottom: _____ T.D. _____

Plugging Completed: 2-1-07

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	430'	None
				4-1/2"	4286'	1630'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed, from _____ feet to _____ feet each set.

Pumped bottom plug with 25 sxs. cement. Cut casing loose @1630', pulled up to 750', pumped 10 sxs. gel& 50 sxs. cement, pulled up to 460', pumped 50 sxs. cement, pulled up to 40' and circulated 25 sxs. cement to surface, 60/40 pos, 6% gel.

Plugging Complete.

Name of Plugging Contractor: Mike's Testing & Salvage, Inc. License #: 31529

RECEIVED

Address: P.O. Box 467 Chase, Kansas 67524

FEB 26 2007

Name of Party Responsible for Plugging Fees: Lotus Operating Co, LLC

KCC WICHITA

State of Kansas County. Rice ss.

Mike Kelso (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.


(Signature) Mike Kelso

(Address) P.O. Box 467 Chase, Kansas 67524

SUBSCRIBED and SWORN TO before me this 22nd day of February, 2006

Irene Herzberg
Notary Public

My Commission Expires: _____



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

AKT