

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Weber Four Oil co., Inc.
Address: 2136 NE Ave, Hoisington, Ks. 67544
Phone: (620) 587-3539 Operator License #: 3585
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 2-16-07 (Date)
by: Case Morris (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Arbuckle Depth to Top: 3398' Bottom: 3306' T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-009-03284-00-00
Lease Name: Holder
Well Number: 1
Spot Location (QQQQ): W/2 - NW - NE - se KCC
3300 Feet from North / South Section Line PKT
2310 Feet from East / West Section Line Pkt
Sec. 12 Twp. 16 S. R. 12 East West RBDMS
County: Barton
Date Well Completed: 8-18-44
Plugging Commenced: 2-16-07
Plugging Completed: 2-16-07

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		0'	490'	8 5/8"	490'	cemented
		0	3398' 3298'	5 1/2"	3398'	none
					KCC PKT 3/2/07 per CP 213 RBDMS	

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

3" EVE stuck in hole at approx. 2000'. Perf tubing at 1500' w/2 holes and 700' w/2 holes. Hookup to 8 5/8' mix 50 sks cement.
Hookup to 3" tubing mix 50 sks, circ.out 5 1/2' annulus.shutin. Mix 75 sks pump down tubing @ 400 PSI.Mix
100 sks w/200# hulls Max PSI 800#. ISIP 700 PSI. All cement 60-40 POZ, 10% Gel.


Name of Plugging Contractor: Quality Oilwell Cementing License #: 31925 Pkt Pkt RBDMS
Address: P.O. Box 32, Russell, Ks. 67665

Name of Party Responsible for Plugging Fees: Weber Four Oil Co., Inc.

State of Kansas County, Russell, ss.

Allen Bangert, Employee of Operator (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Allen Bangert
(Address) _____



SUBSCRIBED and SWORN TO before me this 26 day of Feb, 2007
Brenda Hall Notary Public My Commission Expires: 3-21-09

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
FEB 28 2007
KCC WICHITA Pkt