

**TO:**  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-095-00640-00-00  
Spot: SWNWNE Sec/Twnshp/Rge: 26-30S-8W  
4290 feet from S Section Line, 2345 feet from E Section Line  
Lease Name: WEST SPIVEY UNIT Well #: 18  
County: KINGMAN Total Vertical Depth: 4450 feet

Operator License No.: 32446  
Op Name: MERIT ENERGY COMPANY  
Address: 13727 NOEL RD., STE 500  
DALLAS, TX 75240

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4449		200 SX CMT.
SURF	8.625	200		250 SX CMT. \$ 144.63

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/08/2007 9:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHAR MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (972) 628-1478

Proposed Plugging Method: PERFS 4334'-4344' SAND TO 4284 AND 5 SKS CMT.. REC PIPE. 35 SKS 1250', 35 SKS 700' CIRC 250'-0.

Plugging Proposal Received By: STEVE VANGIESON Witness Type: NONE  
Date/Time Plugging Completed: 02/08/2007 12:30 PM KCC Agent: STEVE VANGIESON

**Actual Plugging Report:**

SANDED BACK PERFS TO 4280', AND CAPPED WITH 5 SKS CMT. NO RECOVERY. PERFED AT 1250 ' SQUEEZED 35SKS CMT INTO PERFS. PEFRD @ 700'. SQUEEZED 35SKS CMT INTO PERFS, PERFED 250' and circ cmt to surface.

**Perfs:**

Top	Bot	Thru	Comments
4334	4344		MISSISSIPPI

**INVOICED**  
DATE 2-21-07  
INV. NO. 2007061371

**RECEIVED**  
**FEB 16 2007**  
**KCC WICHITA**

Remarks: ALLIED CMT CO. - CEMENT COMMON 3% CACL TICKET#24391  
Plugged through: CSG

District: 02

Signed [Signature]  
(TECHNICIAN)

*PLG*