

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-21058-00-00
Spot: N2N2 Sec/Twnshp/Rge: 33-25S-5E
4608 feet from S Section Line, 2801 feet from E Section Line
Lease Name: PIERPOINT A Well #: 112
County: BUTLER Total Vertical Depth: 2150 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PARKWAY, BLDG
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2149		175 SX
SURF	8.625	257		175 SX

\$ 69.88

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: _____
Plug Co. License No.: 30437 Plug Co. Name: UNITED CEMENTING AND ACID CO., INC.
Proposal Rcvd. from: CASEY COATS Company: VESS OIL CO. Phone: (316) 321-4680

Proposed Plugging Method: (1.) Btm plug 50-100' above perf 1962-1982-15-25Sx; (2) Tag btm. Pressure test 100# 5min, (3) perf 250-pump cement to surface.

Plugging Proposal Received By: _____ Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/06/2007 10:45 AM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

2-5-07 Ran in hole with tubing @ 1955', mixed and pumped 50 sxs class A 3% CC. Waited 2 hrs tagged cement @1576. Pumped flag, hole @765. 2-6-07 swedged into 5.5 " casing, circulation & mixed, pumped 422 sxs 60/40/posmix 4% gel to surface. P.A. (pumped 310Sx, reloaded & finish pumping 112 sx= total 422 sxs)

Perfs:

Top	Bot	Thru	Comments
1976	1982		
1962	1966		

RECEIVED
FEB 16 2007
KCC WICHITA

Remarks: UNITED CEMENTING CO. TICKET # 7543 & 7544

Plugged through: TBG

INVOICED
DATE 2-21-07
INV. NO. 2007061372

District: 02

Signed Duane Krueger
(TECHNICIAN)