

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-207-27101-00-00  
Spot: SESENE Sec/Twnshp/Rge: 33-23S-14E  
4210 feet from S Section Line, 250 feet from E Section Line  
Lease Name: HAMMOND Well #: 1  
County: WOODSON Total Vertical Depth: 1710 feet

Operator License No.: 33640

Op Name: HAAS PETROLEUM, LLC

Address: 800 W. 47TH ST., SUITE #409  
KANSAS CITY, MO 64112

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	42	0	

\$ 55.58

Well Type: DH

UIC Docket No:

Date/Time to Plug: 02/12/2007 1:00 PM

Plug Co. License No.: 33557

Plug Co. Name: SKYY DRILLING, LLC

Proposal Rcvd. from: MARK HAAS

Company: HAAS PETROLIUM, LLC

Phone: (816) 531-5922

Proposed Plugging Method: THIS WELL CONSISTED OF AN UNCASSED 6 3/4" BORE TO 1710'. THE PLUGGING PROPOSAL WAS TO PLACE A 50' CEMENT PLUG AT T.D., A 50' CEMENT PLUG AT 750', AND A CONTINUOUS CEMENT PLUG FROM 200; TO SURFACE.

Plugging Proposal Received By: CLAYTON TITEL

WitnessType: PARTIAL

Date/Time Plugging Completed: 02/12/2007 1:15 PM

KCC Agent: CLAYTON TITEL

Actual Plugging Report:

Perfs:

DRILL PIPE WAS RAN INTO THE WELL TO T.D. AND 10 SACKS OF CEMENT WERE PUMPED THROUGH THE PIPE TO T.D.. THE DRILL PIPE WAS PULLED TO 750' AND 10 SACKS OF CEMENT WERE PUMPED THROUGH THE PIPE TO THAT DEPTH. THE PIPE WAS PULLED TO 200'. CEMENT WAS PUMPED INTO THE DRILL PIPE UNTIL CEMENT CIRCULATED FROM THE SURFACE CASING AT SURFACE. THE REMAINING PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE.

RECEIVED  
KCC DISTRICT #3

FEB 14 2007 CPT

CHANUTE, KS

INVOICED  
DATE 2-23-07  
INV. NO. 2007061380

Remarks: WELL GPS'ED ON 02/14/2007 AS HAM 01 AT 38.00809 N & 095.86773 W. CPT

Plugged through: DP

District: 03

Signed Clayton P. Titel  
(TECHNICIAN)

RECEIVED

FEB 20 2007

KCC WICHITA

Form CP-2/3

PST