

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-19015-00-00
Spot: SESE Sec/Twnshp/Rge: 25-19S-22W
660 feet from S Section Line, 660 feet from E Section Line
Lease Name: HUMBURG A-P Well #: 2
County: NESS Total Vertical Depth: 4433 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: BOX 783188 8100 E 22ND ST. N. #700
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	4430	0	WITH 100 SX CMT
SURF	8.625	507		WITH 300 SX CMT \$ 144.07

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/07/2007 11:10 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: BENNIE DILLS Company: RITCHIE EXPLORATION Phone: (316) 691-9500

Proposed Plugging Method: PUMP 200# HULLS & 50 SX CMT. PLUG AT 1600' WITH 30 SX CMT. PERFORATE AT 750'. PUMP CASING VOLUME PLUS 80 SX CMT. USE 150 SX CMT FOR BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/07/2007 4:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RUN TUBING TO 4381' & PUMP 50 SX CMT & 200# HULLS. PULL TUBING TO 1600' & SPOT 30 SX COMMON CMT WITH 3% CC. WAIT 2 HOURS. PRESSURE CASING TO 500#. HELD. RAN BOND LOG & FOUND CMT FROM 1050' TO SURFACE. RAN TUBING TO 1100' & PUMPED 90 SX CMT. CIRCULATED TO SURFACE. PULLED TUBING & TOPPED OFF WITH 15 SX CMT.

Perfs:


Top	Bot	Thru	Comments
4393	4397		

INVOICED
DATE 2-23-07
INV. NO. 2007061393

Remarks: USED COMMON CMT WITH 3% CC & 60/40 POZMIX 6% GEL BY ALLIED.

Plugged through: TBG

District: 01



Signed Michael Maier
(TECHNICIAN)

RECEIVED
FEB 20 2007
KCC WICHITA
Form 2007
PKT