

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-109-20771-00-00  
Spot: SWNWNE Sec/Twnshp/Rge: 1-11S-34W  
1140 feet from N Section Line, 2210 feet from E Section Line  
Lease Name: ANDERSON V Well #: 2-1  
County: LOGAN Total Vertical Depth: 4760 feet

Operator License No.: 5030  
Op Name: VESS OIL CORPORATION  
Address: 1700 WATERFRONT PARKWAY, BLDG  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	372		

\$154.70

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/16/2007 4:00 AM  
Plug Co. License No.: 6039 Plug Co. Name: L.D. DRILLING, INC.  
Proposal Rcvd. from: GREG UNRUH Company: VESS OIL CORPORATION Phone: (785) 443-2435

Proposed Plugging Method: Ordered 200 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: PAT STAAB WitnessType: NONE  
Date/Time Plugging Completed: 02/16/2007 6:00 AM KCC Agent: PAT STAAB

Actual Plugging Report:

1st. Plug at 2675' w/25 sxs.  
2nd. Plug at 1570' w/100 sxs.  
3rd. Plug at 422' w/40 sxs.  
4th. Plug at 40' w/10 sxs.  
Rathole with 15 sxs.  
Mousehole with 10 sxs.

Perfs:

INVOICED  
DATE 2-23-07  
INV. NO. 2007061395

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed \_\_\_\_\_

(TECHNICIAN)

FEB 16 2007

RECEIVED Form CP-2/3  
FEB 20 2007  
KCC WICHITA