

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-24603-00-00
Spot: E2NENESE Sec/Twnshp/Rge: 5-16S-21W
2350 feet from S Section Line, 150 feet from E Section Line
Lease Name: NORMA Well #: 1
County: NESS Total Vertical Depth: 4267 feet

Operator License No.: 5663
Op Name: HESS OIL COMPANY
Address: PO BOX 1009
MCPHERSON, KS 67460

String Size Depth (ft) Pulled (ft) Comment
SURF 8.625 201 WITH 160 SX CMT

\$ 138.68

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 02/11/2007 3:00 AM
Plug Co. License No.: 4958 Plug Co. Name: MALLARD, J. V., INC.
Proposal Rcvd. from: CAROL NICHOLS Company: MALLARD, J. V., INC. Phone: (620) 241-4640

Proposed Plugging Method: 1ST PLUG AT 1740' WITH 50 SX CMT. 2ND PLUG AT 1020' WITH 80 SX CMT. 3RD PLUG AT 570' WITH 50 SX CMT. 4TH PLUG AT 210' WITH 40 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

Plugging Proposal Received By: JERRY W. STAPLETON WitnessType: NONE
Date/Time Plugging Completed: 02/11/2007 5:00 AM KCC Agent: JERRY W. STAPLETON

Actual Plugging Report:


1ST PLUG AT 1740' WITH 50 SX CMT. 2ND PLUG AT 1020' WITH 80 SX CMT. 3RD PLUG AT 570' WITH 50 SX CMT. 4TH PLUG AT 210' WITH 40 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

Perfs:

Remarks: USED 60/40 POZMIX 6% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

District: 01



Signed

Jerry W. Stapleton

PIRT II

(TECHNICIAN)

RECEIVED

FEB 20 2007

KCC WICHITA

Form CP-27

[Handwritten initials]

INVOICED
DATE 2-23-07
INV. NO. 2007061381