

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-039-20996-00-00  
Spot: W2SESWNW Sec/Twnshp/Rge: 10-3S-27W  
2310 feet from N Section Line, 820 feet from W Section Line  
Lease Name: MARTIN Well #: 1-10  
County: DECATUR Total Vertical Depth: 1977 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N. WATER, STE 300  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	288	0	w/200 sxs cmt

\$64.25

Well Type: LH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/03/2007 4:30 PM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: KEITH VANPELT Company: MURFIN DRILLING CO., INC. Phone: (785) 443-1857

Proposed Plugging Method: Ordered 500 sxs of ASC Cement - 2% gel with 1/4# flocele per sack - 250 sxs common - 3% cc. Plug through drill pipe.

Plugging Proposal Received By: HERB DEINES Witness Type: PARTIAL  
Date/Time Plugging Completed: 02/05/2007 5:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Perfs:

8 5/8" surface casing set at 288' w/200 sxs cement.  
Lost circulation at 1932' - dry drilled to 1971' - did not re-gain circulation.  
02/03/2007 - 1630 hrs. Pumped 75 sxs ACS cement at 1971'.  
02/03/2007 - 2130 hrs. Pumped 100 sxs ACS cement at 1935'.  
02/04/2007 - 0230 hrs. Pumped 75 sxs ACS cement at 1930'.  
02/04/2007 - 0830 hrs. Pumped 100 sxs ACS cement at 1930'.  
02/04/2007 - 1230 hrs. Pumped 150 sxs ACS cement at 1930'.  
02/04/2007 - 2200 hrs. Pumped 25 sxs common cement - 3% cc at 1800'.  
02/05/2007 - 0300 hrs. Pumped 50 sxs common cement - 3% cc at 1710'.  
02/05/2007 - 1000 hrs. Pumped 25 sxs common cement - 3% cc at 1500'.  
02/05/2007 - 1300 hrs. Pumped 25 sxs common cement - 3% cc at 1200'.  
02/05/2007 - 1630 hrs. Pumped 40 sxs common cement - 3% cc at 350'.  
02/05/2007 - 1700 hrs. Pumped 10 sxs common cement - 3% cc at 40'.  
Rathole with 25 sxs.  
Mousehole with 10 sxs.

INVOICED  
DATE 2-23-07  
INV. NO. 2007061389

Remarks: ALLIED CEMENTING COMPANY-TICKET #25111-#25112-#25113.

Plugged through: DP

District: 04

Signed Darrel Dipman  
(TECHNICIAN)

RECEIVED

FEB 20 2007

Form CP-2/3

KCC WICHITA

FEB 08 2007

PT