

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-14928-00-02

Spot: SESWSW

Sec/Twnshp/Rge: 25-19S-11W

330 feet from S Section Line,

4290 feet from E Section Line

Lease Name: ISERN

Well #: 4

County: BARTON

Total Vertical Depth: 2347 feet

Operator License No.: 31714

Op Name: NOVY OIL & GAS, INC.

Address: 125 N. MARKET STE. 1230
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
--------	------	------------	-------------	---------

PROD	5.5	2330	2330	when plugged 10/11/1966
------	-----	------	------	-------------------------

SURF	13	200	0	w/unknown sxs cmt
------	----	-----	---	-------------------

76.28

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 02/08/2007 9:00 AM

Plug Co. License No.: 6901

Plug Co. Name: D S & W WELL SERVICING, INC.

Proposal Rcvd. from: ED NEMNICH

Company: D S & W WELL SERVICING, INC.

Phone: (620) 587-3361

Proposed Plugging Method: Ordered 175 sxs 60/40 pozmix - 10% gel - 500# hulls.
09/13/2006 - DS&W cleaned out hole to 2347' - went out of casing.

Plugging Proposal Received By: HERB DEINES

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 02/08/2007 11:15 AM

KCC Agent: PAT STAAB

Actual Plugging Report:

Perfs:

DS&W could only get down hole to 1435'. Hole was filled with heavy rotary mud.
Rigged to tubing - pumped 50 sxs 60/40 pozmix with 100# hulls mixed in.
Pulled tubing to 575'. Rigged to tubing - pumped 35 sxs cement with 100# hulls.
Pulled tubing to 250'. Rigged to tubing - pumped 40 sxs cement with 100# hulls.
Pulled tubing to 40'. Rigged to tubing - pumped 20 sxs cement to circulate cement to surface.
Pulled tubing. Hole standing full.

INVOICED

DATE 2-23-07

INV. NO. 2007061390

2007061400

Remarks: ALLIED CEMENTING COMPANY-TICKET #30577.

Plugged through: TBG

District: 04

Signed

Pat Staab

(TECHNICIAN)

RECEIVED

FEB 20 2007

KCC WICHITA

Form CP-2/3

FEB 12 2007

SINCLAIR PRAIRIE OIL

#L M ISERN

25-19-11W
SE SW SW


BARTON County

Contr.

E 1765 Comm. 9-13-36 Comp. 10-12-36 IP 927 BOPD

Tops	Depth	Datum
ARB	3281 or 3290	
TD	3297	

Casing



INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS